NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shilpa Medicare Limited
Plot # 33, 33A & 40 to 47, Raichur Growth Centre,
Chicksugur Village, Raichur Taluk & District
Karnataka : 584134, India

Date : 21.01.2021
Quote NO : **SQT.20-21.2440**
Kind Attn : Mr.Madhava CH
Email Id : ch.madhav@vbshilpa.com
Contact No: 9035581238

Project Name & Location: Conveyor System, Raichur Taluk & District Karnataka.

Subject : Quotation for Conveyor System

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Conveyor System	1	4,70,976.00	**4,70,976.00**		**25,000.00**
	Total			**4,70,976.00**		**25,000**
2	P&F Charges	3%		**14,129.28**		
	Total Without Taxes			**4,85,105.28**		**25,000**
	GST Extra @ 18%	18%		**87,318.95**		**4,500.00**
	Total With Taxes			**5,72,424.23**		**29,500.00**
3	Transportation Charges			**Extra at Actual**		
4	Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Conveyor System

Parameters	Specification
Product	Solid chemical waste / decanter sludge
Product weight	40-60 kg
Contact parts	MS
Non contact parts	MS
Gear motor	Bonfiglioli 5 HP gear motor
Belt make	PVC belt
Cluster wheel	Nylon wheels
Infeed height	750 mm
Outfeed height	4000mm
Length of conveyor	13000 mm
Movable conveyor	Yes
Belt make	Chiorino/Forbo/NTB
Direction	Unidirectional
Drive roller	200 with rubber coating
Bearing make	SKF/NTN

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd