NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Bigllcoman
Muscat, Oman

Date : 09.04.2020
Quote NO : SQT/19-20/2523
Kind Attn : Mr. D Prasad
Email Id : dprasad@bigllcoman.com
Contact No:

Subject : Quotation for Sectional Door, Dock Leveller, Dock Bumper and Dock Shelter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2,3
C.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in USD		Installation Charges in USD	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Automatic Sectional Door	3000	3000	20	3,535	70,700	Client Scope	
2	Dock Leveller	2000	2500	20	3,667	73,340	Client Scope	
3	Dock Bumper - 450 x 80 x 60 mm			20 Pair	135	2,700	Client Scope	
4	Retractable Dock Shelter	3400	3600	20	1,935	38,700	Client Scope	
				Total		**1,85,440**		
5	P&F Charges			3%		5,563		
	Total With Packing					1,91,003		-
6	Transportation Charges					Extra at Actual		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical Specification -Sectional Door - NIHVA Make

Sr. No	Description	Specification
1	Make	NIHVA Make
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Standard
4	Opening/Closing Speed	0.28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm thick, steel sheet
7	Filling	polyurethane
8	Panel colour	RAL 9002 Grey White Powder coated
9	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
10	Panel Flame Retardent standrad	Flame retardant polyurethane foam
15	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
16	Door saftey	Doors equiped with spring break device
17	Incase of Power failuer	Doors to be equiped with quick release fuction
18	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
19	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
20	Emergency Operation	by Disengagement rope manual
21	Operating Switch	Up/Down Keypad + stopbutton
22	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.

Technical Specification - Dock Leveller - NIHVA Make

SN	Description	Specifications
1	Make	NIHVA
2	Capacity	6 Ton
3	Dock operation mode	AC power pack hydraulically operated
4	Lip operation mode	Hydraulic
5	Operation control	Through panel
6	Loading platform height from road	1250mm
7	Travel above & below dock level	(+) 300 / (-) 250 mm
8	Platform Size (W x L)	2000 mm x 2500 mm
9	Lip size (W x L)	2000 x 400 mm
10	Shut Height	480 mm
11	Overall length	2000 mm x 2500mm + Lip Length (400mm)
12	Maximum slope can be achieved	10%
13	Clear Pit dimensions (W x L x D)	(W) 2040mm x (L) 2500 mm x (D)485 mm
14	Hydraulic power pack	Standard
15	Driver type	Direct by electric Motor
16	Motor Ratings	1 H.P
17	Pump design flow	2.5 LPM
18	Pump pressure	120 bar Operating 200 bar Max.
19	Safety valve set pressure	120 Kg/cm^2
20	Pump Type	Gear
21	Volume of oil receiver	7 Lit
22	No Of Deck cylinder	2 No
23	Lip Cylinder	1 No

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical Specification - Dock Shelter - NIHVA Make

Sr. No	Description	Specification
1	Make	NIHVA
2	Size	(W) 3400 mm x (H) 3600 mm
3	Normal Width x Normal Height	3450 mm x 3400 mm
4	Normal Depth	600 mm
5	Top Curtain	1000 mm
6	Side Curtain	600 mm
7	Curtain Colour	Black
8	Top and Side curtain	Double Layer High Quality Polyester
9	Thickness	3.0mm
10	Frame Material	Aluminum

C) Terms & Conditions

Price	: Ex Works Pune
Frieght	: Excluded
Taxes	: Import taxes/duties excluded.
Delivery	: 6 - 7 weeks for Dock Levellers, Dock Bumper & Dock Shelters and 14-16 weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd