NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0555R4 **Date : 24.03.2017**

ITC - Agri Business Division
Grand Trunk Road,
Nagarampalem, Guntur,
Andhra Pradesh 522004

Kind Attn : Ms. Prasanna Kasha
Email : Prasanna.Kasha@itc.in
Contact No : 8978483409

Project Name And Location : ITC, Guntur

Subject : Quotation for Inflatable Dock Shelter,Motorised Rolling Shutter & Dock Leveller

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication.
Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Assa Abloy Make Dock Shelter**				
1	**Inflatable Dock Shelter** (100% Imported products from Europe) **Size:(W) 3200mm x (H) 3500 mm**	1	No.		-
2	Installation Charges for above Dock Shelter	1	No.		
	Total			.	**-**
B	**NIHVA Motorized Rolling Shutter**				
1	Motorised Rolling Shutter GI Slat:1 mm Thick, Curved Type Profile with heavy duty Shaft, Guide, Hood Cover, Motor – Indirect Drive with painting. Size: (W) 3400 x (H) 3800 mm	1	No.		-
2	Installation Charges for above rolling shutter	1	No.		-
	Total				**-**
C	**NIHVA Make Dock Leveler**				
1	**Capacity: 6 Ton** **Size: (W) 2030mm x (L) 2720mm** 2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up /Down /Lip Up / Down) Rubber Bumpers **(Specifications are attached in mail)**	1	No.		-
2	Installation Charges for above Dock Leveller	1	No.		-
	Total				**-**

VAT TIN :	27545250455 V		**TOTAL BASIC AMOUNT**	**0.00**
CST TIN :	27545250455 C	**Amount in Words :**	**Rupees Seven Lakh Twelve Thousand Only**	
Service Tax No:	AAECN0437HSD001			

Sr.No	Description	Amount	Total
1	Total Supply Amount		
2	CST @ 2%	-	
	Total (A)		-
3	Total Installation charges		
4	Service Tax @ 15%	-	
	Total (B)		-
5	Grand Total (A) + (B)		-

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope

2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	FOR Site
2	**P & F Charges**	:	Nill
3	**Freight Notes**	:	Inclusive in above prices
4	**Delivery**	:	7-8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	100% advance against upply + 100% taxes against delivery at site 100% cost of installation against installation & commissioning
6	**Insurance**	:	Extra As applicable
7	**Sales Tax**	:	CST Extra : 2%
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr. Viraj Motiyale** on 9168937333 For any further Clarification /Information in this concern.

With Best Regards

Monika Kidgaonkar
020-66304033 / 8551091333
For Nihva Technologies Pvt Ltd

395000
175000
102000
672000