NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Vidharbha Cargo Pvt ltd
RAVINDRA TAGO MARG,BLOCK NO. 402
M.G. HOUSE,Nagpur - 440001

Date : 05.11.2020
Quote NO : SQT20-21.2807 - B
Kind Attn : Mr.Ganesh Yadav
Email Id : purchase@xsio.in
Contact No: **9921460973**

Subject : Quotation for ASSA Abloy Crawford Make Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Assa Abloy-Crawford make Dock Leveller - 6 Ton**	2000	2500	10	395,000	3,950,000	20,000	200,000
				Total		**3,950,000**		**200,000**
	P&F Charges			3%		**118,500**		
	Total Without Taxes					**4,068,500**		**200,000**
	GST Extra @ 18%			18%		732,330		36,000
	Total With Taxes					**4,800,830**		**236,000**
	Total Supply + Installation With Taxes							**4,800,830**
2	Transportation Charges					**Extra at Actual**		
3	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA Abloy - Crawford make Dock Leveller





Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Platform Size (W x L)	2000 mm x 2500 mm
3	Travel above & below dock level	(+) 520 / (-) 350 mm
4	Lip size (W x L)	2000 x 400 mm
5	Control Unit Protection Class	IP 54
6	Magnetic Valves	24 V/ DC 18 W S1
7	Nominal Voltage	400 V, 3 Phase
8	Nominal Motor Power	1 HP
9	European Standard	EN 1398

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : Minimum 12-14 weeks after receipt of confirmed Purchase order, Advance Payment and drawing approval

Payment : 80% Advance and Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mrs Sneha Bharane on 8551035333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd