NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Highyield fortune Architects
Mulshi

Date : 04.04.2024
Quote NO : RR_24.25.0004
Kind Attn : Ar. Akshat Agarwal
Email Id : architects@highyield.in
Contact No: 72766 55681

Project Name & Location: Architects Highyeild's project, Mulshi

Subject : Techno - Commercial Offer for Fixed Roof solution and Gate

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR	
		(mm)	(Nos)	Unit Price	Total Amount
1	**Fixed Glass Roof**	• 3300 W X 9900 L • 12mm Toughened Glass • MS Support Structure • Installation Inclusive	1	720,000	**720,000**
2	**Motorized Sliding Gate with Wooden cladding sheet of 10mm thk one sided**	• 5400 W X 2400 L • Installation Inclusive	2	429,000	**858,000**
		Total witout Tax			**1,149,000**
3	GST Extra @ 18%		18%		**Extra At Actual**
4	P&F Charges @ 3%		3%		**Extra At Actual**
5	Support Structure if required @ site				**In Client Scope**
6	Transportation Charges				**In Client Scope**
7	Lifting of Equipments @ Desired floor				**In Client Scope**
8	Unloading Material @ required floor				**In Client Scope**

B) Technical Specification

1. Fixed Glass Roof

1. 12mm Toughened Glass
2. Profile : Powder coated MS Frame
3. Interlocking
4. EPDM Gaskets and sealants
5. SS fasteners

2. Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	80 x 80 x 3.2mm MS SQ. TUBE
6	Inner Tube	32x32x2.0mm
7	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
8	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chrome plated)
9	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
10	Painting	QD Paint & QD Primer
11	El motor make	(100% imported)
12	Emergency Operation	Manual after turn the switch
13	Operating Switch	Push Button from inside
14	Safety	Photocells, Flashing Light
15	Civil work	Client scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the team without completing the work, then extra cost will be applicable for remobilizing the team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. No return policy applicable for customized products.
12. Site readiness delay considered upto 2months only. After that client is totally responsible for any material damage and it will be on chargable basis.
13. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.
Payment :	70% Advance along with Confirmed Purchase Order. 25% After Material Delivery at Site. 5% After Installation.
Validity :	Validity of Offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.
Design Clause :	NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.
Compensation Clause :	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Shilpa R
8551091333
For NIHVA Technologies Pvt Ltd