**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**
**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Infinity Automated solution Pvt. Ltd.**
**Pune**

**Date : 03.03.2020**
Quote NO : SQT.19.20.2367
Email Id : cmd@infinitysols.com
Contact No: 9822603638

**Kind Attn : Mr. Amit Katariya**

**Subject : Quotation for Telescopioc Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|
| | | Total length of conveyor | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Requirement 1- Telescopic Conveyor | 4110 mm | 1 | 11,50,000 | 11,50,000 | 20,000 | |
| 2 | Requirement 2- Telescopic Conveyor | 15 mtr Length (5 mtr Fixed length & 10 mtr Variable Length) | 1 | 21,50,000 | 21,50,000 | 40,000 | |
| | | | **Total** | | **33,00,000** | | |
| | | P&F Charges | 3% | | **99,000** | | |
| | | **Total Without Taxes** | | | **33,99,000** | | |
| | | GST Extra @ 18% | 18% | | 6,11,820 | | |
| | | **Total With Taxes** | | | **40,10,820** | | |
| | | Transportation Charges | | | **In Client Scope** | | |
| | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**
**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**i) Telescopic conveyor - Requiremnt 1**

| Description | Specification |
|---|---|
| Conveyor Type | Flat Belt Conveyor |
| Belt | PVC (Green Belt Texture Belt ,W=700 mm |
| Gearmotor | MGM Vervel make Gearmotor |
| Structure | M.S. Powder Coated |
| Bearing type AT drive end | Pillow Bearing |
| Drive shaft with Roller | MS-Zinc Plated |
| Loading Height | 1600 mm (can be customized ± 50 mm.) |
| Discharge Height | 640 mm Adjustable ± 50 mm |
| Extension Length | Open length 4100 mm ± 50mm |
| Product | Bag of 50 kg |
| Product Size | 920 x 650 mm ( L x W) |
| Application | Unloading of bag from trucks manually |
| Control Panel | Integrated Control panel on conveyor |
| Total Length of Conveyor | 4110 mm |
| Fixed Length | 2000 mm |
| Variable Length | 2110 mm |
| Width of Conveyor | 1550 mm |
| Width of Conveyor Belt | 700 mm |
| Conveyor Capacity | 50 kg/mtr |
| Speed | 10 mtr/min (Variable speed) |
| Conveying | Auto/Manual |
| Telescopic | Auto/Manual |
| Hydraillic Lifting Support | |

**ii) Telescopic conveyor - Requiremnt 2**

| Description | Specification |
|---|---|
| Telescopic Conveyor | 15 mtr Length (5 mtr Fixed length & 8 mtr Variable Length) |
| No of sections | 3 Nos. |
| Load Capacity | 75 Kg/mtr |
| Height of Bed | 900 mm |
| Total Inclined height from Ground | 1650 mm |
| Width of Belt | 600 mm |
| Inclined Conveyor belt width | 800 mm |
| Load of Inclined conveyor | 50 kg/mtr |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**
**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

| | |
|---|---|
| **Price** | : Ex Works Pune |
| **Delivery** | : 10-12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval. |
| **Payment** | : 80% Advance along with Confirmed Purchase Order & Balance before dispatch. |
| **Validity** | : Validity of Offer is 15 days from the date of quotation |
| **Warranty** | : 12 months from the date of supply |

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551093333**

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd