NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TBC
Jalandhar, PB

Date : 26.06.2021
Quote NO : **MHE_21.22.0019**
Kind Attn : Mr. Surjeet
Email Id : surjitdevgun@yahoo.com
Contact No: 9804442000

Project Name & Location: TBC, Jalandhar Punjab

Subject : Quotation for Telescopic Conveyor System

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor System (2 Telescopic conveyor + 1 hood + 1 structure + 1 front conveyor)**	1	28,80,000	28,80,000	85,000	85,000
2	**Koel Genset—40 kVA (Star and Delta connection)**	1	4,80,000	4,80,000		
		Total		33,60,000		85,000
	P&F Charges	3%		1,00,800		
	Total Without Taxes			34,60,800		85,000
	GST Extra @ 18%	18%		6,22,944		15,300
	Total With Taxes			40,83,744		1,00,300
3	Transportation Charges					Extra At Actual
4	Insurance					Extra At Actual
5	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Conveyor System

Sr. No.	Parameters	Specification
1	Material To be Conveyed	HDPE Bags
2	Weight of Bag	40 Kg
3	Collapsed Length	4000 mm
4	Telescopic Length	8000 mm
5	Total Length	12000 mm
6	No. of Extension Stages	3 from either side
7	Belt Gear box make	SEW/Bonfiglioli/PBL
8	Belt Speed	Please specify
9	Belt Direction	Bi-directional for loading and unloading
10	Power Supply	240 VAC, 50 Hz
11	Electric component make	Siemens/Schnieder

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd