WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
M/s Fuji Silvertech concrete Pvt Ltd	
Address:	
309 ,Summit the Business Bay , Off. Western Express Highway , Mumbai-400057	

PO Number:	FSCPL/21-22/PM013	W. O. No-	SO/21-22/0060
PO Dated :	22.07.21	W. O. Date	22.07.2021
PO Received Date:	22.07.21	Sales Co ordinator	Pradeep
Ref. Quotation:	SQA.21.22.0146R1	Front Sales Person	Shrikant

Contact Details		Dispatch Address:
Contact Person:	Keyur Bhatt	Fuji infrastructure Technologies Pvt Ltd,Sector No-11 , plot No-2 Auric shendra Aurangabad Dist -
Email ID of contact Person:		
Mobile No:		

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Motorised Single Leaf Sliding Gate	**Motorized Sliding Gate** Size considered -Clear opening - (W) 12500 mm x (H)2000 mm **Opening Direction**-Horizontal - from left to right or reverse **Design Pattern**-Standard Tubular Design Pattern **Outer Tube** -100 x 100 x 3.6 mm MS SQ. TUBE **For Post**- 100 x 100 x 3.6 mm MS SQ. TUBE **inner Tube**-40 x 40 x 3.2 MS SQ. TUBE **Gap Between Tubes**-125mm **Bottom Rail on ground**- dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams. **Bottom Rollers**-Heavy Duty Bottom Wheel With both side Bearings (chorme plated) **Guide Rollers supporter during Gate movement** - Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate **Painting** -2 Coats of EPOXY polyamide based enamel finish of approved colour **El motor make** - European Make (100% imported) **Emergency Operation** - Manual after turn the switch	Nos	1			-	Pending
2	Manual Single Leaf Wicket Gate	**Manual Single Leaf Wicket Gate** Clear opening - (W) 2000 mm x (H)2000 mm **Design Pattern**-Standard Tubular Design Pattern **Outer Frame Tube Sizes** -100 x 100 x 3.6 mm MS SQ. TUBE **Internal Vertical Tube Sizes**-40 x 40 x 3.2 MS SQ. TUBE **Gap Between Tubes**-100 mm **Painting** -2 Coats of EPOXY polyamide based	Nos	1				Pending
						Total	-	

Non standard items/extra requirement,

B Commerical Terms:

1	Payment Terms:	20% advance along with P.O , 80% payment against PI before dispatch & 10% after compilation of installations & commisioning work at site		
2A	Delivery Date as per PO:	Within 4-5 Weeks from the date of issuing P.O	2B. Required Delivery Date:	
3A	Transportation Scope:	Client scope - At actual	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	NIHVA	5B. Loading Charges:	
6A	Unloading Scope:	CLIENT	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	CLIENT	7B. Available Lifting Equipments	
8	Warranty:	12 months from the date of Handing Over		
9A	Height arrangement Scope:	NA	9B. Available Equipments for working at Site:	
10	Electricity Supply:	CLIENT		
11	GST:	As Applicable		
12A	Installation Scope:	NIHVA	12B. Installation required date:	
13	Mode of import:	NA		
14	HSS:	NA		
15	Documentation Required:	Warranty Certificate, MTC, Inspection reports, User Manual		
16A	Total site visits required:	-	16B. Site visit charges:	

Certified that the above work order finalised in presence of:

ACCOUNTS	AGM	SALES	Sores / MFG	Operation	PROJECT	DESIGN	Purchase	Date & Time
O.S.	A.K	P.S.	G.B. / R.W.	K.P.	P.J.		A.M.	7/26/2021