NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ASSA ABLOY Entrance Systems
P.O.Box 80983Dubai Investment Park 1
Dubai,U.A.E.

Date : 12.07.2022
Quote NO : MHE_22.23.0018
Kind Attn : Mr. Vishnu Vinod
Email Id : bsarnobat27@gmail.com
Contact No: 8007862050

Project Name & Location: ASSA ABLOY Entrance Systems, Dubai, UAE

Subject : Commercial Offer for Pit Monuted Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in Doller USD (Ex.works Pune)		Installation Charges in Doller USD	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Monuted Hydraulic Scissor Lift** • Capacity 2500 Kg • Lifting Height: 1700 mm • Close height: 650 mm • Safety Bellows	2000 L mm X 2000 W mm	1	9,666	9,666	In Client Scope	
			Total		**9,666**		
			Total Without Taxes				**9,666**
2	GST Extra @ 18%		18%				**Extra At Actual**
3	P&F Charges on Total Supply Value		3%				**Extra At Actual**
4	Transportation Charge						**In Client Scope**
5	Unloading Charges @ Site						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Pit Monuted Hydraulic Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	2500 Kg
2	**Platform size**	(L) 2000 mm X (W) 2000 mm
3	**Shut Height**	650 mm
4	**Lift Height from ground level**	1700 mm
5	**Lip size**	250 X 2000 mm
6	**Lip Operation**	Hydraulic
7	**Type of platform**	Chequred plate with 8mm thickness
9	**Railing**	2-Side Fixed Railings, Height 900 mm
10	**Safety Feature**	Safety Bellows
11	**2- Push Button for up & down operation**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil/masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price :	Ex Works Pune.
Inco Terms :	Ex Works Pune.
Delivery :	5-6 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval excluding selling period.
Payment :	80% Advance along with Confirmed Purchase Order. 20% Along with Approval of Drawing and before start a Production.
Validity :	Validity of Offer is 7 days from the date of quotation
Warranty :	12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd