WORK ORDER

NIHVA

Client:	
Finearc System Pvt Ltd	
Address:	
Gat. No. 408, village Urawade Taluka Mulshi, Pune - 412108	

PO Number:	220629	**W. O. No-**	SO/22-23/072
PO Dated :	10-02-2023	**W. O. Date**	10-02-2023
PO Received Date:	10-02-2023	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQA.22.23.362R	**Front Sales Person**	

Dispatch Address:

Gat. No. 408, village Urawade Taluka Mulshi, Pune - 412108

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Machine Protection Doors (W)2000 mm X (H)2070 mm** (High Sea Sale)	**Door version :**Vertical Rapid Roller Door for machine protection. **Side Frames :**Aluminum anodized two parts, to have easy access to switches and service. **Door blade:**Rolltex Plus Curtain (RAL2009) **Bottom beam:** Aluminium anodized. **Drive unit:** Drive unit IP 55, Motor on LH with control cable (standard length = height of door) **Opening / closing speed:** Approx. max. 2,4 / 1,7 m/s **Control system:** MCC Frequency converterVector Control for opening/closing speed up to 2,4 / 1,4 m/s for door with safety contact edge, protection IP 55. Without display, interface card delivered separately, including power- and interface cable, with main switch in separate box. **Power suppy:** 3L(N)PE 380/400/415/440/460 and 480 V, 50/60 Hz **Safety features:** Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection. **Safety limit switch:** 1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space. **Window Type:** 700 x 500 mm Anti UV Type **Motor & Hood Cover:** Included , **Motor at LHS** **Display :** Display "Up-Stop-Down" **Interface Card :** MCC without display unit, with combibox in plastic (175x250x150 mm) with interface card and main switch included in combibox, including power- and interface cable.	Nos	2		0	-	Pending
						Total		-

Non standard items/extra requirement, if any:	**Please Mention PO Number on Delivery Challan,Client Reqt:- TEST CERTIFICATE**

B Commerical Terms:

1	**Payment Terms:**	30% Advance against OA and Balance 30 Days PDC against receipt of Material.		
2A	**Delivery Date as per PO:**	On or Before 05-04-2023	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	CLIENT Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	CLIENT Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	CLIENT	**12B. Installation required date:**	
13	**Mode of import:**	Sea		
14	**HSS:**	Yes		
15	**Documentation Required:**	High Sea Sale documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

GM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		Shilpa	Sandip	Sujata	11-02-2023