NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JMC PROJECTS (INDIA) LIMITED
C/o. NATIONAL MINERAL DEVELOPMENT CORP.
BLOCK-B, NMDC Iron and Steel Plant,
NAGARNAR, JAGDALPUR, BASTAR,CHHATTISGARH -494001

Date : 03.07.2020
Quote NO : SQT.19.20.2636
Kind Attn : Mr. Muzaffar Madni
Email Id : Muzaffar.Madni@jmcprojects.com
Contact No: 8291349534

Project Name & Location: Pune.

Subject : Quotation for Fire Rated Motorised Rolling Shutter and sliding Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Motorised Rolling Shutter**	10000	3450	2	462,000	924,000	20,000	40,000
2	**Fire Rated Motorised Rolling Shutter**	3850	2500	2	196,000	392,000	20,000	40,000
3	**Fire Rated Motorised Rolling Shutter**	4200	2500	1	206,000	206,000	20,000	20,000
4	**Fire Rated Motorised Rolling Shutter**	5700	2500	2	246,000	492,000	20,000	40,000
5	**Fire Rated Motorised Rolling Shutter**	2500	2500	3	180,000	540,000	20,000	60,000
6	**Fire Rated Motorised Rolling Shutter**	2400	1400	2	168,000	336,000	20,000	40,000
7	**Fire Rated Motorised Rolling Shutter**	2000	2100	2	176,000	352,000	20,000	40,000
8	**Manual Single Leaf Sliding Gate**	4000	2700	1	351,000	351,000	20,000	20,000
9	**Wicket Gate**			2	42,000	84,000	20,000	40,000
			Total Value			**3,677,000**		**340,000**
			P&F Charges	3%		110,310		
			Total Without Taxes			**3,787,310**		**340,000**
			GST Extra @ 18%	18%		681,716		61,200
			Total With Taxes			**4,469,026**		**401,200**
			Total (Supply + Installtion) with Taxes					**4,870,226**
10	Transportation Charges					**In Client Scope**		
11	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Design:
Roll formed from 1st grade BHP Zincalume steel curve slat curtain

Guide Rail:
Fabricated from hot-dipped galvanized steel of 3.0mm with one-piece design surface mounted type

Bottom Bar:
Assembled of 2 pieces of 38x38x3mm galvanized steel angle bolted 800mm pitch with galvanized bolts and nuts or 2 pieces of 40x40x6mm steel flat bar.

Shutter Enclosure Box:
Fabricated from heavy duty 7.0mm steel plate for both ends and supports with steel frame with very well black primer one coat. Box covers shall be of 0.8mm steel sheets with BHP zincalume finishing.

Motor Drive Unit:
- **Power Source:**
  230v 50Hz 1 phase
- **Manual Chain Override**
- **One-unit push button switch**
- **Gravity drop level**
- **Fire Shutter will autoclose via 71 Degree Celcius Thermal Fusible Link**
- **Auto close by relay switch after receive of 24vdc fire signal**

Standard RAL colors:
- **RAL 1015**
- **RAL 7025**
- **RAL 9010**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Sliding Gate	
Door type	**Manual Single Leaf Sliding Gate**
Clear Opening gate dimension	(W) 4000 x (H) 2700...in mm
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
OUTER PIPE	OD76.2 X 3.2 THK
INNEAR PIPE	OD50.8 X 3.2 THK
Gap Between Tubes	125 MM
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 10 - 11 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333.**

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd