NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Technology Nucleus
1, Pranav Apartments, Guru Ganesh Society,
Bibwewadi - Kondhwa Road,
Pune 411037

Date : 09.03.2021
Quote NO : **AS_20.21.0003R2**
Kind Attn : Rahul Bhalgat
Email Id : rahul.bhalgat@technologynucleus.com
Contact No: 9890053053

Project Name & Location: Loading Conveyor, Pune

Subject : Quotation for Loading Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Loading Conveyor**	1	5,53,300.00	**5,53,300.00**	**Client Scope**	**Client Scope**
	Total			**5,53,300.00**		
	P&F Charges	3%				**In Client Scope**
	Total Without Taxes			**5,53,300.00**		
	GST Extra @ 18%	18%		**99,594.00**		
	Total With Taxes			**6,52,894.00**		
2	Transportation Charges					**In Client Scope**
3	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Conveyor System

Parameters	Specification
Product	Dry concrete, like stones
Product size	Granuels
Product weight	350kg
Product capacity	Please specify
Conveyor capacity	Upto 400kg
Speed of Conveyor	Upto 20mtr/min
Conveyor Infeed height	2400 mm
Conveyor Outfeed height	2400 mm
Contact parts	MS powder coated
Non-contact parts	MS powder coated
Gear Motor	Bonfiglioli
Foot	Spectra plast/equivalent
Belt with bottom profile	PVC green belt (2M10-U0-V10
Belt Make	chiorino (Italy)
Belt width	500 mm
Conveyor width	700 mm aprox
Finish	Powder coated
Speed control through	VFD(optional)
Hopper capacity	1350kg
Hopper MOC	MS powder coated

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd