NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

CICON ENGINEERS PVT. LTD
CICON HOUSE" No.61/2,
Doddakallasandra, Gubblala Cross,
Kanakapura Road, Bangalore - 560 062.

Date : 20.11.2020
Quote NO : SQT.20.21.2831
Kind Attn : Tanuja M S
Email Id : techcicon@gmail.com
Contact No: 080-22560622

Project, Location : Embassy, Shoolgiri Hosur.

Subject : Quotation for Motorized Rolling Shutter, Sectional Door, Dock Leveler and Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	2500	3000	1	95,000	95,000	20,000	20,000
2	**Motorized Rolling Shutter**	4000	5000	1	150,000	150,000	20,000	20,000
3	**Sectional Door Vertical Lift**	2500	3000	1	251,000	251,000	20,000	20,000
4	**Sectional Door Vertical Lift**	4000	5000	1	492,000	492,000	20,000	20,000
5	**Dock Leveler - 6 Ton**	2000	2500	96	200,000	19,200,000	15,000	1,440,000
6	**Dock Bumpers (Set)**			1	6,000	6,000	4,000	4,000
7	**Motorized Single Leaf Sliding Gate**	6000	1500	1	280,000	280,000	20,000	20,000
8	**Motorized Single Leaf Sliding Gate**	6000	1800	1	283,000	283,000	20,000	20,000
9	**Wicket Gate**	1200	1800	1	40,000	40,000	10,000	10,000
	Total			**104**		**20,797,000**		**1,574,000**
10	P&F Charges			3%		623,910		
	Total Without Taxes					21,420,910		1,574,000
	GST Extra @ 18%			18%		3,855,763.80		283,320
	Total With Taxes					**25,276,674**		**1,857,320**
11	Transportation Charges					Extra at atcual		
12	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA ASSA ABLOY Sectional Door

Sr. No	Specification	Sectional Door
1	**Vision Windows**	2 Nos at central panel
2	**Opening Direction & Mounting**	Vertical lift
3	**Opening/Closing Speed**	CDM9 0,28 m/s
4	**Door Material**	GI Steel
5	**Panel Thickness**	42 mm Square Grid, steel sheet
6	**Filling**	CFC-free polyurethane
7	**Panel colour**	RAL 9002 Grey White Powder coated
8	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
9	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.
10	**Water Penetration**	EN 12425 class 3
11	**Air Permealibity**	EN12426 class 3
12	**Wind Load**	EN21424 class 3
13	**Thermal Transittance**	EN 12428 1.10W /m2K
14	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	**Door saftey**	Doors equiped with spring break device
16	**Incase of Power failuer**	Doors to be equiped with quick release fuction
17	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
18	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
19	**Emergency Operation**	by Disengagement rope manual
20	**Operating Switch**	Up/Down Keypad + stopbutton
21	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
22	**Environmental Green Product Declaration Certification**	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler

Sr .No.	Specification	Dock Leveller
1	**Capacity**	6 Ton
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2000 mm x 2500 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2000mm x 2500mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	0.1
12	**Clear Pit dimensions (W x L x D)**	(W) 2050mm x (L) 2550 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No
23	**Yellow and Black Strips for Side**	Included
24	**Operation**	not stopping automatic while any truck movement

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	**Door type**	Motorized Single Leaf Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	72 x 72 x 3.2mm MS SQ. TUBE
6	**For Post**	72 x 72 x 3.2mm MS SQ. TUBE
7	**Innear Tube**	25 X 25 X 2.6 MM THK SQ. TUBE
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd