Sales Quotation

Quotation No - SQT/20-21/2764 **Date : 13.10.2020**

FEV India Pvt. Ltd.
Plot No. A-21, Talegaon MIDC
Tal Maval Dist. Pune 410507

Kind Attn: Shashikant Jagtap
Email: jagtap@fev.com
Contact No: 8390952225

Project Name And Location : Pune

Subject : Quotation for Pallet Conveyor Solutions and Turn table

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
	Pallet Conveyor System				
A	**Chain Conveyor - 1000 mm Length**				
B	**Chain Conveyor - 1500 mm Length**				
C	**Roller Conveyor**				
D	**Turn Table**				
1	**Specification:** Product : Pallet Product Size max :(L) 950 x (W) 800 x (H) 700 mm Product weight : 350 kgs Conveyor capacity : Up to 500 kgs Speed of Conveyor :12-15 min/ mtr Conveyor Infeed Height : 500 mm Conveyor outfeed Height : 500 mm Contact Parts : M S Powder coated Non Contact Parts : M S Powder coated Gear Motor : Bonfiglioli Foot : Spectra plast/equivalent Chain : Duplex Chain Belt Make : Diamond Conveyor Width : As per layout Finish : Powder coated Speed Control : Through VFD (optional) PLC : Siemens Sensor : P&F/equivalent Panel : Rittal / equivalent Turn Table rotation through : Servo	1	No	1,750,000	1,750,000
2	Installation for Conveyor System	1	No	246,485	246,485
3	Hand Shaking	1	No	80,000	80,000
				Total	**2,076,485**

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**2,076,485**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3%
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Rohit - 7410175333** For any further Clarification /Information in this concern.

With Best Regards

Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd