Sales Quotation

An ISO 9001:2008 Certified Company

Quotation No - SQT/19-20/1806R2 **Date :06-08-2019**

INDOSPACE
One Indiabulls Centre, 11th Floor, Tower 2A,
Senapati Bapat Marg, Elphinstone Road,
Mumbai - 400013, India.

Kind Attn: Mr. Tushar Dhande
Email: tushar.dhande@indospace.in
Contact No : 8879311890

Project Name And Location :Chakan.

Subject : Quotation for Rolling Shutter, High Speed Door, Dock Leveller and Dock Shelter.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
Double Wall Motorised Rolling Shutter					
A	**Double Wall Motorized Rolling Shutter** **Technical Specifications:** **• GI Slat : 19 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **• Vision Window of two Rows** **(Supply + Installation+ Transportation)**				
1	Size (W) 5000 mm x (H) 5000 mm	6	No	293,700	1,762,200
2	Size (W) 3600 mm x (H) 5000 mm	3	No	227,700	683,100
3	Size (W) 3600 mm x (H) 4500 mm	1	No	211,700	211,700
4	Size (W) 2400 mm x (H) 3000 mm	2	No	128,700	257,400
				Total	**2,914,400**
B	**Gear Operated Rolling Shutter** **Technical Specifications:** **• GI Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover :0.9 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation + Transportation)**				
1	Size (W) 2000 mm x (H) 3000 mm	3	No	77,000	231,000
2	Size (W) 3000 mm x (H) 3000 mm	3	No	91,000	273,000
3	Size (W) 2251 mm x (H) 2415 mm	1	No	72,000	72,000
4	Size (W) 2000 mm x (H) 2200 mm	1	No	67,000	67,000
				Total	**643,000**

High Speed Door					
C	**Nihva Make Rapid Roll Up Door (Wind Class - 2)** **(Component Imported from Europe)** **(Supply + Installation + Transportation)**				
Basic Equipment :	High-Speed Roller Door with PVC curtain.				
Drive Unit :	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Power supply :	3/(N)/PE/230/400/415 v; 50 Hz				
Safety :	Safety contact edge, Safety photocell transmitter / receiver inside side columns.				
Loop Detector	Magnetic Loop Detector - Both Side				
Traffic Light	Red & Green - Traffic light				
	Top Cover Inclusive				
	Motor cover Inclusive				
1	**Size : (W) 4000 mm x (H) 4500 mm**	3	No	392,250	1,176,750
2	**Size : (W) 3600 mm x (H) 4500 mm**	5	No	338,250	1,691,250
3	**Size : (W) 2500 mm x (H)2500 mm**	1	No	285,250	285,250
				Total	**3,153,250**
D	**Assa Abloy Make Dock Shelter - DS6070E** **Inflatable Dock Shelter (100% Imported products from Europe)** **(Supply + Installation + Transportation)**				
1	Size : (W)3600 mm x (H)3755 mm	4	Nos.	406,500	1,626,000
				Total	**1,626,000**
E	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers.** **(Supply + Installation + Transportation)**				
1	**Dock Leveler Capacity 6 Ton** Size : (W) 2000 mm X (L) 2500 mm X (H) 480mm	3	No	**194,500**	583,500
2	**Dock Leveler Capacity 9 Ton** Size : (W) 2000 mm X (L) 2500 mm X (H) 480mm	1	No	**209,500**	209,500
				Total	**793,000**
F	**Optional Accessories for Dock Leveler**				
1	**Articulated Arm, LED Dock Light**	4	No	**25,000**	100,000
				Total	**100,000**
				Grand Total	**9,229,650**
				GST 18%	**1,661,337**
				Grand Total Including Taxes	**10,890,987**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	At Site.
2	**P & F Charges**	:	NIL.
3	**Freight Notes**	:	Inclusive.
4	**Delivery**	:	9-10 Weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil** on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd