NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mr. Sagar Deshmukh
Pune

Date : 17.05.2023
Quote NO : RR_23.24.0028
Kind Attn : Mr. Sagar Deshmukh
Email Id : sagar.d@wipropari.com
Contact No: 9822604824

Project Name & Location: Glass House, Pune

Subject : Commercial Offer for Glass House at your Existing Bunglow

Dear Sir ,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	General Conditions	2
C.	Terms & Condtions	2

A) Commercial Offer

Sr. No.	Description	Size (mm)		Qty	Supply & Installation Charges in INR		
		Actual Size	Standard Size	(Nos)	Rate	Sq. Ft.	Total Amount
1	MS TUBE 100X100X4MM THK. - SUPPLY AND FABRICATION OF MS STRUCTURE WITH COAT OF PRIMER AND PU PAINT, ALL AS PER APPROVED DRAWING. (RATE/KG)	0X0	0.00X0.00	1	300.00	890.00	2,67,000
2	UPVC SLIDING WINDOW 3T3S WITH 11.52MM CLEAR TGH. LAMINATED GLASS	2300X4300	2362.00X4343.00	2	1300.00	220.84	2,87,092
3	UPVC SLIDING WINDOW 3T3S WITH 11.52MM CLEAR TGH. LAMINATED GLASS	2300X3900	2362.00X3962.00	1	1300.00	100.73	1,30,949
4	UPVC FIX GLASS WITH 11.52MM CLEAR TGH. LAMINATED GLASS	1000X4300	1067.00X4343.00	2	1300.00	99.76	1,29,688
5	UPVC FIX GLASS WITH 11.52MM CLEAR TGH. LAMINATED GLASS	1000X3900	1067.00X3962.00	1	1300.00	45.50	59,150
6	UPVC FIX GLASS WITH 11.52MM CLEAR TGH. LAMINATED GLASS	1000X2800	1067.00X2819.00	1	1300.00	32.38	42,094
7	UPVC FIX GLASS WITH 11.52MM CLEAR TGH. LAMINATED GLASS	2300X2800	2362.00X2819.00	1	1300.00	71.67	93,171
8	UPVC FIX GLASS WITH 11.52MM CLEAR TGH. LAMINATED GLASS	1000X900	1067.00X914.00	1	1300.00	10.50	13,650
9	UPVC SWING DOOR ON FLOOR SPRING WITH 11.52MM CLEAR TGH. LAMINATED GLASS	2300X1000	2362.00X1067.00	1	1800.00	27.13	48,834
	Total without Tax						**10,71,628**
10	GST Extra @ 18%				18%		**Extra At Actual**
11	P&F Charges @ 3%				3%		**Extra At Actual**
12	Transportation Charges						**In client Scope**
13	Lifting Equipment required @ desired floor						**In client Scope**
14	Support Structure if required @ site						**In client Scope**
15	Unloading Charges @ Site						**In client Scope**

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.
12. Amount can increase or decrease as per the actual work done at site, management won't be responsible for any amount changes & dear client please check the quantity at your end.
13. We charge as per standard size in 3, 6, 9, 12 inch.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

C) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.

Payment : 70% Advance along with Confirmed Purchase Order.
20% After material Delivery at site.
10% After completion of Installation.

Validity : Validity of offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

Design Clause : NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.

Compensation Clause : Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Urmila Ghotre
7410169333
For NIHVA Technologies Pvt Ltd