Plot No. 149/1, Sector No. 7, PCNTDA, Bhosari, Pune - 411026.
Mb. : 94225 12489 / 97666 25828.
Email: mallesh@malgudicranes.com
www.malgudicranes.com

MALGUDI Associates

Ref: 55/21-22/M -408 Date: 31th Jan 2022

TO,

NIHVA TECHNOLOGIES

Thermax Chouk.

Kind Attention: - Mr. Dnyaneshwar Kumbhar.

Ref: Your Enquiry Date: - 28 th Jan 2022.

Sub: - Offer for **SG Goliath Crane 5 MT.**

Dear Sir,

We thank you for your email enquiry for **SG Goliath Crane 5 MT** …. Based on the details of your enquiry, we have considered your specific requirements and are pleased to submit our detailed offer as per the enclosed **ANNEXURE-1 & ANNEXURE – 1 STC**.

1. ANNEXURE –1 Detailed offer, covering technical details
2. ANNEXURE – 1 STC covering general standard terms and conditions

The above two Annexure form integral part of our offer.

We shall be at your disposal for any technical / commercial clarification and/or information with respect to this offer.

Thanking you,

Yours truly,

For MALGUDI ASSOCIATES.

Mallesh B.K.

Technical Specifications – 5 MT	
Crane Capacity	5 MT
Span.	5 Mtr.
Class of Duty	Class- II as per IS 807/3177
Operation	From Floor Through Pendant Push Button Control
Location	Indoor
Protection	IP55
Height of Lift.	6 Mtr.
Hoist Make	Malgudi / Modular Type
Main Hoisting Speed.	3/1 M/Min Micro With VFD
Cross travel Speed	20/5 M/Min Micro With VFD
Long travel Speed	20 / Min Micro With VFD.
Main hoist motor rating.	4 KW X 1 NOS. (Make – SEW / NORD)
Cross travel motor rating	0.37 KW X 1 NOS. (Make – SEW / NORD)
Long travel motor rating	0.55 KW X 2 NOS. (Make – SEW / NORD)
All motor types	Sq. cage, Crane Duty Motors, 40% CDF, 150 Sts/hr, make SEW/ NORD GERMANY, Or BNFIGLIOLY ITALY
Main Hoist, Cross Travel & Long Travel Brake Type.	Inbuilt D.C disc type.
Number of Falls	4 FALLS
Wire Rope Construction	10 mm / 6x36
Cross Travel Wheel Diameter	130 MM x 4NOS.
Long Travel Wheel Diameter	200 MM x 8 NOS.
Total Crane Weight	@ 2.84 MT
Wheel Load Without Impact	@ 3.938 MT
All Wheels	Double flanged, OPEN DRIVE.
Hook	Hook Single shank forged, Swiveling type
Painting	As Per You Requirement Enamel Std. Paint
Gantry rail	40 x 40 mm
Bay-length	30 Mtr.
Electrical Panel	All Switch Gears And VFD Schneider Make
Cables	All Flat Cable, Top Make
CT Festooning	C Rail Festoon
LT Power Supply	Cable Reeving Drum / Busbar / Cabling
Safety Features	Obstruction Sensor, Pendent Control, Hooter, Limit Switches For All Motion
Quantity	1 No's

ANNEXURE –1

Name of the customer	NIHVA TECHNOLOGIES
RFQ No. / Date	Your Enquiry Dtd. 28th Jan 2022.
Our offer No.	408/2020-2021--DT: 31th Jan 2022.

SG Goliath Crane 5 MT				
Sr. No.	**Description**	**Qty**	**Supply (EX Work Basis)**	**Amount**
1	Design, Manufacturing And Supply of Single Girder Goliath Crane 5 MT As per Above Specifications, Along With Malgudi Make Wire Rope Hoist.	1 Nos.	8,89,625 / Nos.	8,89,625
2	Design, Manufacturing And Supply of Rail Track Arrangement For 30 Mtr. Bay Length,	1 Nos.	2,56,830 / Nos.	2,56,830
3	Supply And Installation of Crane And Rail Track Arrangement *Note – Considering Installation Is In Pune Region.	1 Nos.	75,000 / Nos	75,000
TOTAL				**12,21,455**

NOTE:

1. **Mobile Crane for Unloading & Installation Is in Your Scope.**
2. **Main Electrical Supply Is In Your Scope.**
3. **Transportation Is In Your Scope.**

For MALGUDI ASSOCIATES

Akshay Salunkhe
8380000859

Prepared by:	Technical details approved:	Quote approved:
ARS	MBK	MBK

MALGUDI

ANNEXURE-1 STC

Name of the customer	NIHVA TECHNOLOGIES
RFQ No. / Date	Your Enquiry Dtd. 28th Jan 2022.
Our offer No.	408/2020-2021--DT: 31th Jan 2022.

GENERAL TERMS AND CONDITIONS

1. **VALIDITY:**
   The offer is valid for **30 days** from the date of receipt.

2. **DELIVERY TERMS:**
   Delivery will be 6 to 7 weeks from date of firm P.O.

3. **PRICE BASIS:**
   The quoted prices are on each **Ex-work**, basis.

4. **PACKING & FORWARDING:**
   Packing & Forwarding **@2%,** extra, Freight Charges at actual extra.

5. **INSURANCE:**
   To be arranged by you.

6. **GST TAX: @18%**

7. **PAYMENT TERMS:**

   Our Payment terms will be:

   i) 40% Advance along with Purchase Order.

   ii) 50% on completion of stage wise Inspection.

   iii) 10% Against Pro forma invoice.

Payment terms to be discussed & mutually agreed between **MALGUDI ASSOCIATES** and NIHVA TECHNOLOGIES

MALGUDI

ANNEXURE-1 STC

Name of the customer	NIHVA TECHNOLOGIES
RFQ No. / Date	Your Enquiry Dtd. 28th Jan 2022.
Our offer No.	408/2020-2021--DT: 31th Jan 2022.

GENERAL TERMS AND CONDITIONS

8. INSPECTION:

At Our Works.

9. GUARANTEE:

Product supplied by us shall be guaranteed for material of construction, good workmanship & against any design deficiency for the period of 12 months from The Date of Dispatch.
Equipment guarantee is valid against defective workmanship and / or poor performance of the system only. Our liability is limited to repair or replace the same and not subject to any wear/tear or supply of consumables/spares.

10. DEVIATIONS:

In case of any deviations or additions required in the specifications/drawings, there will be Consequent delay in delivery of the item. Cost implication due to Changes effected will be extra as mutually agreed.

For MALGUDI ASSOCIATES.

Akshay Salunkhe
8380000859

Prepared by:	Technical details approved:	Quote approved:
ARS	MBK	MBK