NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SERUM INSTITUTE OF INDIA PVT LTD
Hadapsar
Pune 411028

Date : 13.03.2021
Quote NO : SQT.20.21.2773R7
Kind Attn : Mr. Pradip Paithane
Email Id : pradip.paithane@seruminstitute.com
Contact No: 9881836006

Project Name & Location: Hadapsar

Subject : Revised Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specifications	2
C.	General Conditions	3
D.	Terms & Conditions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Teckentrup make Double Skin Motorised Rolling Shutter - 100% Imported from Germany with MS Structure**	4515	8200	10	860,000	8,600,000	35,000	350,000
				Total		**8,600,000**		**350,000**
2	P&F Charges on Total Supply Value			3%		258,000		
	Total					**8,858,000**		**350,000**
	GST Extra @ 18%			NIL		Due to SEZ		
3	Transportation					**Inclusive**		
4	Unloading Charges @ Site					**Inclusive**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double Skinned Teckentrup Rolling Shutter with MS Structure

Sr .No.	Specification	Double Skinned Teckentrup Rolling Shutter with MS Structure
1	Door Curtain	ThermoTeck steel filled with PU-foam
2	Roller door surface outside	Galvanised with protective fill
3	Door Colour Inside/ Outside	Uniformly
4	Buffer Drive side min/exist.	300 mm / 300 mm
5	Buffer bear side min./exist.	175 mm / 175 mm
6	Lintel height min./ exist.	680 mm / 680 mm
7	Insertion Depth	948 mm
8	Building Structure	Concrete
9	Bottom Profile	ET-1 for Teckentrup ThermoTeck
10	Welding Shaft	Steel Tube 159 mm primed
11	Guide rail	FS 85 steel
12	Underlining Size	60 mm
13	Console Drive/ Bearing Side	Console Type 7.5
14	Brush sealing Type	BH - 50
15	Drive Type	Direct Mount Drive TAR 5.75 KU 400 V/3Ph AWG 12 U/min; IP54; 60% ED
16	Drive mounted	Inside Left, standing
17	Emergency Drive Operation	Crank Handle
18	Door operation	Normal operation quantity CS310 (Pulse) with built in triple button CEE plug with wire
19	Safety edge device:	opto-sensors
20	Control Cable length	9000 mm
21	Wind resistance:	Wind load resistance class 2
22	Heat transmis value (W/m2K)	3,34
23	Structure for fixing Rolling Shutter 4515 mm X 8200 mm	
24	Material Mild Steel	
25	Structure made from ISMC 100 / TUBE 100 as per availability	
26	Structure weight 300 KG	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	Client Scope
4	Any civil / masonry/structural work required	Client Scope
5	All structure support required	NIHVA Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	Client Scope
7	Conduits, Cables required	Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 -12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order and Balance before disptach

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd