NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Wooshin Engg.Pvt.Ltd
Gat.No.581/1,2&715 | A/P Wadhu Bk
Near Koregoan Bhima,Nagar Road|
Tal.Shirur Dist.Pune 412216

Date : 22.09.2020
Quote NO : SQT/20-21/2703R
Kind Attn : Mr Sushant Sawalekar
Email Id : sushant.sawalekar@wooshin.co.in
Contact No: 7030915792

Subject : Quotation for High Speed Door RP300

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Option 1 :** **Albany make Machine Protection Door (RP300)**	2000	2000	10	7,38,000	73,80,000	20,000	2,00,000
2	**Option 2 :** **NIHVA make Machine Protection Door**	2000	2000	10	3,97,000	39,70,000	20,000	2,00,000
			Total			-		-
3	P&F Charges			3%		-		
	Total Without Taxes					-		-
4	Transportation Charges					Extra at actual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Details	
		Albany make Machine Protection Door RP300	**NIHVA make Machine Protection Door NTP333**
1	Door version:	**Vertical Rapid Roller Door for machine protection.**	**Vertical Rapid Roller Door for machine protection.**
2	Side Frames:	**Aluminum anodized two parts, to have easy access to switches and service.**	**Aluminum anodized two parts, to have easy access to switches and service.**
3	Door blade:	**Rolltex Plus Curtain with RAL Blue 5002**	**2mm thick Curtain with RAL Blue 5010**
4	Bottom beam	**Aluminium anodized.**	**Aluminium anodized.**
5	Drive unit:	**Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)**	**Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)**
6	Opening / closing speed:	**Approx. max. 2,4 / 1,7 m/s**	**Approx. max. 2,0 / 1,5 m/s**
7	Control system:	**MCC Vector Control**	**MR220 Controller with Inverter**
8	Power suppy:	**3/(N)/PE 230/380/400/415 V, 50 Hz**	**3/(N)/PE 230/380/400/415 V, 50 Hz**
9	Safety features:	**pre running photocell.**	**Safety edge with cable chain integrated in side frames, pre running photocell.**
9	Photocell	**with Photocell**	**with Photocell**
10	Safety limit switch:	**1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.**	**1 Euchner safety limit switch .**
11	Window Type	**700 x 500 mm Anti UV Type**	**700 x 500 mm Anti UV Type**
12	Window Qty	**1 No**	**1 No**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

Note: **Please find below List which are in Client Scope**

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) **Terms & Conditions**

Price : Ex works Pune

Delivery : 12 - 13 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd