HORIZON CHUTES PVT. LTD.

HCPL/ FD/INTRO/133/16-17 **Date – 25th October 2016**

NIHVA TECHNOLOGIES PVT.LTD
8/1, Coromant CHS, Sector 27, Pradhikaran,
Pimpri-Chinchwad Road, Nigadi,
Pune Maharashtra 411014 India

Sub: Quotation of Fire Door & General Purpose Doors.

K. A: Mr. R.A. Dange (85551098333)

Dear Sir,

We are into manufacturing of different products which are enhancing the utility and safety in the built environment. Our metal fire doors are tested successfully in ARAI (Automotive Research Association of India), Pune laboratory, as per British Standard BS 476 (Part 20 & 22), 1987/ IS3614. We are manufacturing Fire door sets in our State of Art manufacturing unit by using CNC controlled machines to produce quality fire doors.

We are manufacturing: -

1) **Metal Fire Doors (60/120/240 Min).**
2) **Wooden Fire Doors (30/60/90/120 Min).**
3) **Sliding Doors (120/240 Min).**
4) **Trap Doors (60/120/240 Min).**
5) **Glazed / Glass Fire Doors & Partitions (120 Min).**
6) **Blast Resistance Doors.**

We are OEM for Promat Asia Pacific for manufacturing Wooden Fire Doors Glass Fire Doors, Sliding Doors, etc.

Thanking you and assuring our very best always,

For HORIZON CHUTES PVT.LTD.

Gat No.6B, Plot No.2, Kasurdi Khe Ba, Shivapur Saswad Rd.,
Tal: Bhor, Dist: - Pune, Pune: - 411205
Ph. 91 20 24252441, Cell 0 8308908811
Email: salesmumbai@horizonchutes.com Website: www.horizonchutes.com

TABLE – 1 - TECHNICAL SPECIFICATIONS

INPUT DATA – BASIS OF DESIGN FOR FIRE DOORS

1	Fire Doors tested according to	BS 476 part (20 & 22) tested at ARAI (Automotive Research Association of India) (Certificate No – CAE/6380/2009-10/4(V1)/60B dated 11th May 2010
2	Fire rating	120 Minute (2 Hours) for Integrity and stability
3	Material of Construction	Galvanised Steel and Mild Steel
4	Type of Doors	Single leaf and Double leaf
5	Frame	Thickness – 1.5 mm thk. sheet (Single or Double Rabbet)
6	Door	Thickness – 46 mm manufactured in 1.2 mm thk. Sheet
7	Infill	Rock wool
8	Finish	Powder Coating in various colour options
9	Hinges	SS Ball bearing hinges suitable for door thickness
10	Hardware Optional	Fire rated hardware such as Panic devices, External Devise, Mortise Locks, Cylinder Locks, Hydraulic Doors Closers, Concealed Tower bolts & Vision Panels can be used as per service requirements

TABLE – 2 - TECHNICAL SPECIFICATIONS FOR -NON FIRE DOORS (General Purpose Doors)

INPUT DATA – BASIS OF DESIGN

1	Material of Construction	Galvanised Steel and Mild Steel
2	Type of Doors	Single leaf and Double leaf
3	Frame	Thickness – 1.2 mm Thk. sheet (Single or Double Rabbet)
4	Door	Thickness – 46 mm manufactured in 0.8 mm thk. Sheet
5	Infill	Rock wool
6	Finish	Synthetic Enamel paint in various colour options
7	Hinges	SS Ball bearing hinges suitable for door thickness
8	Hardware Optional	Fire rated hardware such as Panic devices, External Devise, Mortise Locks, Cylinder Locks, Hydraulic Doors Closers, Concealed Tower bolts & Vision Panels can be used as per service requirement

TABLE – 3

SCOPE OF SUPPLY –

1.0	**Complete Door set as per requirement along with required planned hardware.**

Following is the list of exclusions from our scope

EXCLUSIONS

1	**All what so ever Civil Scope needed at site for erection of doors such as giving clear cut out in wall, Concrete filling in frames, etc.**
2	**Free Power connection at alternate floor for erection activities at site**
3	**Free Secured storage place for storage of materials before site erection at your site**
4	**Any other item not listed in our scope**

TABLE – 04. – OFFER (Attached**)**

1. **Annexure 1- Offer for Fire Door**
2. **Annexure 2- Offer for Metal Door**
3. **Annexure 3- Offer for Hardware**

Deviation 05

Frame Thickness – 1.5 mm thick for fire rated door.

TABLE -06- TERMS & CONDITIONS

DELIVERY: Delivery within 5 -6 weeks from the date your PO with all technical clarification, drawing approval and advance payment received whichever is later.

A) PAYMENT TERMS

- **50% Advance with Purchase order.**
- **50% Before Dispatch Against PI.**

B) Validity of Quotation – 15 Days.

C) Warranty – 1 Year against manufacturing defect only on door from the date of Installation & no warranty on hardware.

D) Labour Union & Mathadi at your (Builders) account (Strictly).

E) Unloading & shifting the material at desired location in client's scope.

F) Any third party charges other than the offer will be in client's scope.

G) Taxes as applicable during invoicing as per government regulation.

H) Installation & Transportation in client scope.

I) To & Fro Charges, accommodation charges in Clint scope.

J) LBT, Octroi & other third party charges if required will be client scope strictly.

K) Cement Grouting is not is our scope.

We hope that you will find our offer in line with your requirement and request you to please give us a chance to serve your organisation.

For, HORIZON CHUTES PVT. LTD.

Sunil Ambike.
9960690633