NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Horizon Chutes Pvt. Ltd
11/16/2, Village Nanded,
Off Pune Sinhgad Road,
Pune – 411041

Date : 04.07.2020
Quote NO : SQT/20-21/2629R
Kind Attn : Mr.Mahesh Limaye
Email Id : info@horizonchutes.com
Contact No: 98220 37079

Subject : Quotation for Hermetic Sealed Sliding Door and Non - Hermetically sealed Manual door .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specifications	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Hermetically Sealed Sliding Doorr**	1400	2100	3	94,500	283,500	25,000	75,000
2	**Hermetically Sealed Sliding Door**	1800	2100	3	169,500	508,500	25,000	75,000
3	**Non - Hermetically sealed Sliding Door**	1400	2100	2	92,000	184,000	25,000	50,000
4	**Non - Hermetically sealed Sliding Door**	1800	2100	2	165,750	331,500	25,000	50,000
				Total		**1,307,500**		**250,000**
5			P&F Charges	3%		39,225		
			Total Without Taxes			1,346,725		250,000
			GST Extra @ 18%	18%		242,410.50		45,000
			Total With Taxes			**1,589,136**		**295,000**
6			Transportation Charges			In Client Scope		
7			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specifications

1	Hermetically Sealed Sliding Door	Providing and fixing of Hermetically Sealed Sliding Doors with core of 60 MM thick built up with 04 mm thick HPCL sheet as skin at both side of the door. CFC-free, high density polyurethane puff (Density 45 kg/m3) as infill, to provide better insulation. Door Profile of 2.5 mm thick special grade 6063-T6 aluminium extrusion with natural shade anodizing finish of 15 microns. The cavity free design of profiles makes the door ROBUST in its segment league. Door Sealing made with 3-tier specially designed 3 side heavy duty replaceable EPDM gasket (60 degree shore) against wall frame. Bottom sealing with 2-tier heavy duty EPDM gasket to flush with finished floor. High grade (6063-T6) Aluminum Extrusion with natural shade anodized 15 micron. Wall frame profile is 3-sided blind fixed with cladding on wall cutout section from inside and outside of the room. For easy & smooth door opening special handle. Vision glass of size 350x350 mm.

2	Non Hermetically Sealed Sliding Door	Providing and fixing of Hermetically Sealed Sliding Doors with core of 60 MM thick built up with 04 mm thick HPCL sheet as skin at both side of the door. CFC-free, high density polyurethane puff (Density 45 kg/m3) as infill, to provide better insulation. Door Profile of 2.5 mm thick special grade 6063-T6 aluminium extrusion with natural shade anodizing finish of 15 microns. The cavity free design of profiles makes the door ROBUST in its segment league.High grade (6063-T6) Aluminum Extrusion with natural shade anodized 15 micron Wall frame profile is 3-sided blind fixed with cladding on wall cut-out section from inside and outside of the room. For easy & smooth door opening special handle. Vision glass of size 350x350 mm.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4 - 5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd