**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune :**

## NIHVA Sales Quotation

**IKEA India Private Limited**
10th Floor, Greenheart - Phase IV
Mfar Manyata Tech Park, Nagawara
Bangalore, Karnataka – 560045, INDIA

**Date : 08.05.2021**
Quote NO : AS_20.21.0001R
**Kind Attn :** Mr. Pavan Kumar B S
Email Id : pavan.kumar2@ingka.ikea.com
Contact No: 9535500991

**Project Name & Location: Mumbai**

**Subject : Quotation for Manual Mobile Scissor Table**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 1 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | |
|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount |
| 1 | **Manual Mobile Scissor Lift Table**<br>Platform Size = 1400 mm L X 900 mm W<br>Capacity = 500 KGS<br>Shut Height = 400 mm<br>Max Height = 1300 mm<br>Lift Height = 900 mm<br>Hand pump for lifting operation<br>Push pull handle provided for Manual Movement<br>Wheels : Dia 150 x 50 ( PU Wheels)<br>Color : Golden Yellow OR Ultra Marin Blue | 6 | 1,45,000 | 8,70,000 |
| | | **Total** | | **8,70,000** |
| | P&F Charges on Total Supply Value | 3% | | **26,100** |
| | **Total Without Taxes** | | | **8,96,100** |
| | GST Extra @ 18% | 18% | | **1,61,298** |
| | **Total With Taxes** | | | **10,57,398** |
| 2 | Transportation Charges | | | **Extra At Actual** |
| 3 | Unloading Charges @ Site | | | **In Client Scope** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**
**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification -**

**Manual Scissor Lift Table**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Capacity | 500 KG |
| 2 | Platform size | 1400 mm L X 900 mm W |
| 3 | Closing Height | 400 mm |
| 4 | Max Height | 1300 mm |
| 5 | Lift Height | 900 mm |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune :**

**C) General Conditions**

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | |
| 4 | Any civil / masonry/structural work required | |
| 5 | All structure support required | |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | |
| 7 | Conduits, Cables required | |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 50% Advance along with purchase order and Balance against material dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551093333**

With Best Regards
Prtaibha Mete
8530872333
For NIHVA Technologies Pvt Ltd