NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Megawide Construction
PO bag No-1 , Greenfield international airport MOPA,
Nagzer Permem , Goa -403512

Project, Location : GMR GOA INTERNATIONAL AIRPORT LIMITED

Date : 22.07.2022
Quote NO : SQT.22.23_0114 R2
Kind Attn :
Email Id :
Contact No:

Subject : Revised quotation for Motorized Sliding Gate , Swing Gate and Manual Wicket Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Leaf sliding Gate**	4500	1620	4		-	Included	
2	**Motorized Bi-parting Swing Gate**	4500	2600	4		-	Included	
3	**Manual Swing wicket gate**	1000	1400	2		-	Included	
	Total			**10**		**-**		
4	P&F Charges							
5	Freight charge							
	Total Without Taxes					**-**		**-**
	Discount			**7.5%**		**-**		
	Total after discount					**-**		
	GST Extra @ 18%			18%		-		-
	Total With Taxes					**-**		**-**
6	Transportation Charges				Included			
7	Unloading Charges @ Site				In Client Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Single Leaf sliding Gate

Sr .No.	Specification	Motorized Single Leaf sliding Gate
1	**Door type**	Motorized Single Leaf sliding Gate
2	**Clear Opening gate dimension**	(W) 4500 mm X (H) 1620 mm
3	**Master Leaf Size**	5800 X 1620 mm
4	**Opening Direction**	Horizontal - from left to right or reverse
5	**Mounting Location area**	Inside area
6	**Design Pattern**	Standard Tubular Design Pattern
7	**Outer Frame Tube Sizes**	50 x 50 x 3 mm MS Sq Tube
8	**Internal Vertical Tube Sizes**	25 x 25 x 3 mm MS Sq Tube
9	**For Post**	50 x 50 x 3 mm MS Sq Tube
10	**Distance between two tubes**	As per drawing
11	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
13	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	**Painting**	Epoxy Paint
15	**Control Panel**	1 No Operating Station.
16	**Operation**	By Electric Motor (European Make) - Rack and Pinion Mechanisam
17	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4 Photocell
17	**Civil work**	**Client scope – client need to grout the I beam in concrete to create track for sliding gate**

Manual Swing wicket gate

Sr .No.	Specification	Manual Swing wicket gate
1	**Door type**	Manual Swing wicket gate
2	**Clear Opening gate dimension**	(W) 1000 mm X (H) 1400 mm
3	**Opening Direction**	Inside or Outside - 90 deg angle
4	**Mounting Location area**	Inside
5	**Design Pattern**	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	50 x 50 x 3 mm MS Sq Tube
7	**Internal Vertical Tube Sizes**	25 x 25 x 3 mm MS Sq Tube

Quoted Products as per drawing provided by Client , Specifications Please check before finizaltion

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Bi-parting Swing Gate

Sr .No.	Specification	Motorized Bi-parting Swing Gate
1	**Door type**	Motorized Bi-parting Swing Gate
2	**Clear Opening gate dimension**	(W) 4500 mm X (H) 2600 mm
3	**Leaf Size**	2250 X 2600 mm each leaf
4	**Opening Direction**	90 deg angle Inside
5	**Mounting Location area**	Inside area
6	**Design Pattern**	Standard Tubular Design Pattern
7	**Outer Frame Tube Sizes**	50 x 50 x 3 mm MS Sq Tube
8	**Internal Vertical Tube Sizes**	25 x 25 x 3 mm MS Sq Tube
9	**Distance between two tubes**	As per drawing
10	**Cladding**	2 mm MS sheet cladding on Both Side
11	**Bottom Rollers**	Not recommended (Due to small opening)
12	**Painting**	Epoxy Paint
13	**Control Panel**	1 No Operating Station.
14	**Operation**	By Electric Motor (European Make)
15	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4 Photocell

Quoted Products as per drawing provided by Client , Specifications Please check before finizaltion

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Included

Delivery : 5-6 weeks for Gates from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order, 40% before dispatch and 10% after Installation Immediately.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd