NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rohan Builders (India) Pvt. Ltd
1 Modibag,Commercial Building,
Ganeshkhind Road, Shivaji Nagar,
Pune – 411 016

Date : 08.04.2021
Quote NO : SQT.20.21.3128 R
Kind Attn : Ajay Mahade
Email Id : inquiry.ho@rohanbuilders.com
Contact No: 9860502997

Project, Location : M/s. Flex Food Ltd. At Near Hosur, Tamil Nadu.

Subject : Revised Quotation for Rolling Shutters ,Sliding Gate , HSD ,Dock Leveler & Dock Bumper

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MS Gear Operated Rolling Shutter**	3000	4000	1	60,000	60,000	10,000	10,000
2	**GI Motorised Rolling Shutter**	3000	4000	1	88,000	88,000	10,000	10,000
3	**GI Perforated Motorised Rolling Shutter**	3000	4000	1	100,000	100,000	10,000	10,000
4	**Nihva Make - High Speed Door**	2700	3500	5	298,000	1,490,000	15,000	75,000
5	**Nihva Make Dock Leveler- 15 ton**	2000	2500	2	190,000	380,000	20,000	40,000
6	**Nihva Make Dock Leveler- 15 ton**	2000	3000	3	210,000	630,000	20,000	60,000
7	**Automatic Sliding Gate**	13500	2000	1	340,000	340,000	15,000	15,000
8	**Automatic Sliding Gate**	10000	2000	1	290,000	290,000	15,000	15,000
9	**Dock Bumper - 1 Pair**	(W)150 x (D) 80 x 400 (H) mm		1	7,000	7,000		-
	Total			**16**		**3,385,000**		**235,000**
10	P&F Charges			3%		101,550		
	Total Without Taxes					**3,486,550**		**235,000**
	GST Extra @ 18%			18%		627,579.00		42,300
	Total With Taxes					**4,114,129**		**277,300**
11	Transportation Charges					**Extra at atcual**		
12	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Gear Operated Rolling Shutter

Sr .No.	Specification	MS Gear Operated Rolling Shutter
1	**Description:**	Gear Operated Rolling Shutter with MS Laths with thickness of 1.0 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0 mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -As per the opening width dimension
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint
13	**Drive Unit & Mounting Type**	Gear Assembly

Motorised Rolling Shutter / Perforated Motorised Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description:**	Gear Operated Rolling Shutter with GI Laths with thickness of 1.0 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0 mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -As per the opening width dimension
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	Powder Coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection
14	**Perforated Area**	1000 mm Height

Nihva Make High Speed Door

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening / Closing speed	Opening / Closing speed 0.8 m/s.
4	Control Panel	4 Push Button operated
5	Resistance to wind load	EN12424 upto class 2
6	Curtain	Fabric Transparent PVC section
7	Curtain colour	Standard blue RAL 5010
7	Guide Material	Galvanised steel.
8	Hood Cover	GI
9	Motor Cover	GI
10	Operator & Control	German Make Motor
11	Connecting Voltage	400 V ~ / 50 - 60 Hz
12	Open-Stop-Close Button	Standarad
13	Protection Category	IP 54
14	Power Consumption	0.75 kw Motor
15	Emergency Off Button	Standard
16	Closing Zone Monitoring	Optical Safety edge
17	External Route Monitoring	Photocell
18	Emergency Opening	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Nihva Make Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	15 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from	1250mm
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Platform Size (W x L)	2000 mm x 3000 mm
9	Lip size (W x L)	2000 x 400 mm
10	Shut Height	480 mm
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
13	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)3000 mm x (D)480 mm
14	Hydraulic power pack	Standard
15	Driver type	Direct by electric Motor
16	Motor Ratings	1 H.P
17	Pump design flow	2.5 LPM
18	Pump pressure	120 bar Operating 200 bar Max.
19	Safety valve set pressure	120 Kg/cm²
20	Pump Type	Gear
21	Volume of oil receiver	7 Lit
22	No Of Deck cylinder	2 No
23	Lip Cylinder	1 No

Automatic Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
6	For Post	72 x 72 x 3.2mm MS SQ. TUBE
7	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5-6 weeks for Dock Leveler & rolling shutter , 8-9 Weeks for Sliding Gate & 10-12 Weeks for High Speed door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd