NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon Pvt. Ltd.
Pune

Date : 21.08.2019
Quote NO : SQT.19.20.1948
Kind Attn : Mr. Nikhil Bakane
Email Id : nbakane@suroj.in
Contact No: **020 41355926**

Project Name & Location: CN IFFCO PRIVATE LIMITED, PUNJAB

Subject : Quotation for Rolling Shutter, High Speed Door, Sectional Door, Sliding Door, Dock Leveller, Dock Shelter, Turnstile & Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 & 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI 1mm Motorised Rolling Shutter	4000	4500	1	2,33,000	2,33,000	20,000	20,000
2	GI 1mm Gear Operated Roling Shutter	4000	4500	1	1,01,000	1,01,000	20,000	20,000
3	High Speed Door HS9020G (Albany Make)	3000	4000	1	5,18,000	5,18,000	20,000	20,000
4	Sectional Door	3000	4000	1	3,20,000	3,20,000	20,000	20,000
5	Automatic Sliding Glass Door	3000	4000	1	2,26,000	2,26,000	20,000	20,000
6	Dock Leveller 6 Ton	2200	3000	1	1,90,000	1,90,000	20,000	20,000
7	Dock Leveller 10 Ton	2200	3000	1	2,10,000	2,10,000	20,000	20,000
8	Retractable Dock Shelter (ASSA Abloy)	3400	3500	1	1,34,000	1,34,000	20,000	20,000
9	Tripod Turnstile			1	71,000	71,000	15,000	15,000
10	Boom Barrier 6 Mtr			2	1,30,000	2,60,000	20,000	40,000
			Total			**22,63,000**		**2,15,000**
3	P&F Charges			3%		**67,890**		
	Total Without Taxes					**23,30,890**		**2,15,000**
	GST Extra @ 18%			18%		4,19,560		38,700
	Total With Taxes					**27,50,450**		**2,53,700**
4	Transportation Charges					**In Client Scope**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1	**GI Motorised Rolling Shutter**

• GI Slat:1 mm Thk
• Flat Type Profile with heavy duty Shaft, Guide
• Hood Cover 0.9 mm thick
• Motor - Indirect Drive
• Powder Coating

2	**GI Gear Operated Rolling Shutter**

• GI Slat:1 mm Thk
• Flat Type Profile with heavy duty Shaft, Guide
• Hood Cover 0.9 mm thick
• Gear Assembly
• Powder Coating

3	**High Speed Door (HS9020G)**

Description	**Specification**
Structure:	Galvanized steel
Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
Safety	Photocells in side columns Flexible soft bottom edge including wireless edge activator Break-away and self-repair function
Options	Different vision options are available.
Wind load resistance	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
Lifetime expectations	1.000.000 cycles
Thermal transmittance	6,02 W/(m²K)

4	**Vertical Scetional Doors**

• Sectional door with Vertical Lift
• Vision Windows
• Motor & control Panel
• Bottom safety edge and with all safety features

5	**Sliding Glass Door**

• Main power supply
• Operator type- Bi part operator
• Glass : 10mm thick toughened glass
• 100% imported from Sweden

6	Dock Leveller

1 & 2 Dock Leveler	
Description	**Specifications**
Capacity	6 Ton & 10 Ton
Dock Operation Mode	AC power pack hydraulically operated
Lip operation mode	Hydraulic
Operation control	Through panel
Loading platform height from road	1250mm
Travel above & below dock level	(+) 300 / (-) 250 mm
Platform Size (W x L)	2200 mm x 3000 mm
Lip size (W x L)	2200 x 400 mm
Shut Height	480 mm
Overall length	2200mm x 3000mm + Lip Length (400mm)
Maximum slope can be achieved	0.1
Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 3050 mm x (D)485 mm
Hydraulic power pack	Standard
Driver type	Direct by electric Motor
Motor Ratings	1 H.P
Pump design flow	2.5 LPM
Pump pressure	120 bar Operating 200 bar Max.
Safety valve set pressure	120 Kg/cm²
Pump Type	Gear
Volume of oil receiver	7 Lit
No Of Deck cylinder	2 No
Lip Cylinder	1 No
Dock Bumper	Pair of Dock Bumper

7	Dock Shelter

Specification	NIHVA Assaabloy Rectractable Dock Shelter
Door type	Dock Shelter DS6060A
Clear Opening dimension	Size:(W) 3200 mm x (H) 3250 mm : 1 Nos
Curtain colour	Black
Parking Guides	White, Yellow
Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
Top & Side Curtaiins	Double Layer High Quality Polyester
Thickness	3.0 mm
Weight	Approx 3400 g/m2
Continous Roof Cover	One layer high quality Polyester
Thickness	0.5 mm
Weight	Approx 680 g/m2

8	Tripod Turnstile

Description	Specification
Size (L x B x H)	480 x 280 x 980 mm
Unlock Time	0.2 Sec
Pass Rate	35 person / min
Pass Width	550 mm
Weight	45 Kg
Mode	Fail Safe
Power Consumption	30 W
Driving voltage	24 V

9	Boom Barrier

Description	Specification
Control Unit	Libra C MV
Motor Power Supply	24Volt
opening or closing Time	6 sec
Type of Limit Swaitch	Electronic
Slowdown	Adjustable
Lock	Mechanical
Release	Personal Relese Key

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Swapnil Kulat on 7219207333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd