NIHVA TECHNOLOGIES

WEIGHT ESTIMATION SHEET

CLIENT		DATE	24-04-2024
PROJECT	Motorised Sliding Mega Door	LOCATION	Pune
FINISH SIZE	25 m x 6.0 m	PREPARED BY	Sumit

SR	DESC	DETAILS	MATERIAL GRADE	SP.GRAVITY	DIA	WIDTH	HEIGHT	THICKNESS	LENGTH	UOM	QUANTITY	WEIGHT	REMARK
1	SINGLE LEAF (4300 mm X 6000 mm)	Tube - Outer Frame	MS	7.85		100	50	3.2	123600	mm	1	892	2530
		Horizontal Tube Support	MS	7.85		100	50	2	121200	mm	1	200	Weight OF leaf
		Inner Tube Support	MS	7.85		40	20	2	363600	mm	1	238	
		Puff Panel	PUFF	1.2		1160		50	150	M	1	1200	
2	Bottom Track	En 8 Bright Hardchrome Bar	En8	7.85	25				80	M	1	311	
		If ISMC C channel 100 x 50 x 5 in our scope	MS	7.85					80	M	1	848	
3	Top Track	Roller Track	MS	7.85		100	50	3.2	80	M	1	640	
4	Accessories	Bottom Side wheel Assembly (4 inch)	MS	7.85						No's	12	0	
		Top Roller Assly	MS							No's	12		
										Weight For Required Qty	1	4329	
										Weight Including Safety Factor	1.5	6494	

Mode Of Operation = Motorised

Motor Selection = According | 1800 Kg | Qty - 02

REFERENCE IMAGE

