NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

INOX AIR PRODUCTS Corporate Office
Plot NO A2. TTC Industrial Area, Pawne, MIDC Off
Thane Belapur Road, Opp. Gami Industrial Park,
Kopar Khairane, Navi Mumbai, 400710

Date : 14.1.2021
Quote NO : SQT.20.21.2949
Kind Attn : Arpana Singh
Email Id : arpana.singh@inoxap.com
Contact No: 9833074766

Subject : Quotation for Motorized Telescopic Three Leaf Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MOTORISED TELESCOPIC THREE LEAF SLIDING GATE	6000	1800	1	548,000	548,000	20,000	20,000
				Total		**548,000**		**20,000**
2	P&F Charges			3%		16,440		
	Total Without Taxes					564,440		20,000
	GST Extra @ 18%			18%		101,599.20		3,600
	Total With Taxes					**666,039**		**23,600**
3	Transportation Charges					Extra at actual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Clear Opening gate dimension**	(W) 14000 mm X (H) 1800 mm
3	**Master Leaf Size**	3200 X 1800 mm
4	**1 ST Leaf Size**	3060 X 1800 mm
5	**2 ND Leaf Size**	3060 X 1800 mm
6	**Opening Direction**	Horizontal - from left to right or reverse
7	**Mounting Location area**	Inside area
8	**Design Pattern**	Standard Tubular Design Pattern
9	**Outer Frame Tube Sizes**	100 X 100 X 3.6 MM THK SQ. TUBE
10	**Internal Vertical Tube Sizes**	40 X 40 X 2.6 MM THK SQ. TUBE
11	**For Post**	100 X 100 X 3.6 MM THK SQ. TUBE
12	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
13	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
14	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
15	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
16	**Control Panel**	2 Nos Operating Station.(Motor Panel and Security Room)
17	**Operation**	By Telescopic Mechanism
18	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd