NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Kumar World
Pune

Date : 11.03.2021
Quote NO : SQT.20.21.2885R2
Kind Attn : Rohit Sardesai
Email Id : Rohit.Sardesai@Kumarworld.com
Contact No: 7304940259

Subject : Revised Quotation for Double Leaf Telescopic Sliding Gate, Single Leaf Sliding Gate and Wicket Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Double Leaf Telescopic Sliding Gate	7000	2000	1	581,000	581,000	20,000	20,000
2	Single Leaf Sliding Gate	5000	2000	1	374,000	374,000	20,000	20,000
3	Wicket Gate	1200	2000	1	50,000	50,000	10,000	10,000
				Total		**1,005,000**		**50,000**
4	P&F Charges			3%		30,150		
	Total Without Taxes					1,035,150		50,000
	GST Extra @ 18%			18%		186,327.00		9,000
	Total With Taxes					**1,221,477**		**59,000**
5	Transportation Charges					In Client Scope		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	Door type	Motorised Double Leaf Telescopic Sliding Gate
2	Master Leaf Size	5000 X 1875 mm
3	1 ST Leaf Size	4400 X 1875 mm
4	Opening Direction	Horizontal - from left to right or reverse
5	Mounting Location area	Inside area
6	Design Pattern	As per drawing
7	Outer Frame Tube Sizes	100X50X4 THK SQ. TUBE
8	Internal Vertical Tube Sizes	100X50X3.2 MM THK SQ. TUBE
9	For Post	100X100X4 MM THK SQ. TUBE
10	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
11	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
12	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
13	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
14	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
15	Operation	By Telescopic Mechanism
16	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Hooter
		4. Photocell

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	As per drawing
5	Outer Tube	100X50X4 THK SQ. TUBE
6	For Post	100X100X4 MM THK SQ. TUBE
7	Innear Tube	100X50X3.2 MM THK SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

Wicket Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Mounting Location area	Inside area
3	Design Pattern	As per drawing
4	Outer Frame Tube Sizes	100X50X4 THK SQ. TUBE
5	Internal Vertical Tube Sizes	100X50X3.2 MM THK SQ. TUBE
6	Gap Between Tubes	100 mm C/C
7	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
8	Operation	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Amol Gaware on 7758820333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd