HAFELE INDIA PVT. LTD.
Office No. 3, Building A
BETA, I Think Techno Campus
Off J.V.L.R., Opp. Kanjurmarg Station
Kanjurmarg (East)
Mumbai 400 042
India

Reference No. HIPL-MW-NHIVA Pune -2023

To,
NHIVA
Pune

Date: 06-08-2024

We thank you for your enquiry for the NHIVA , Pune project and are hereby pleased to submit our offer for supply & installation of HAFELE MOVABLE WALLS as follows:

Hafele Worldwide

With its origin in 1923 in Swabian region of Germany, Hafele has lived up to its roots through a successful presence in architectural and furniture hardware industry for over several decades now.

Today, Hafele's worldwide penetration includes 38 subsidiaries across Europe, America, Asia, Australia and New Zealand. With its subsidiaries and numerous other sales organizations, Hafele operates in over 150 countries. The Hafele headquarters, 4 manufacturing units and 10 sales offices are located within Germany; while 1 manufacturing unit is located in Budapest, Hungary. The Hafele worldwide workforce is empowered by a base of over 7600 employees. The group services over 150,000 customers across the globe through its extensive range of hardware products and a comprehensive logistics system.

Hafele is a family owned and run business with a unique, friendly and value-centric work culture which is strongly followed among all its subsidiaries

Hafele India

Hafele India is a wholly owned subsidiary of the Hafele Global network and has been operating in India since 2003. The subsidiary has a strong nation-wide presence with offices in Mumbai, Pune, Ahmedabad, Bangalore, Chennai, Hyderabad, Delhi and Kolkata. It has full-scale operations in Sri Lanka and Bangladesh with Regional Offices and Design Showrooms in both the countries; and has also spread its sales operations to other countries in South Asia including Nepal and Bhutan

Hafele India services its customers with a base of over 850 employees, a well-networked franchisee base of over 80 shops, along with over 100 dealers situated across South Asia. The subsidiary has a sophisticated logistics centre in Mumbai along with distribution centres in Delhi, Bangalore, Kolkata and Colombo.

Movable Wall Systems by Hafele

Hafele brings to you its range of movable wall systems from Parthos, Netherlands. These systems are ideal for space management within a given area to achieve optimal space utility. Our range of movable wall systems gives you the flexibility of customization and conforms to highest standards of functionality and quality

Palace 80, 90 and 110 provides the possibility of having solid partitions that are extremely easy and smooth in its operation and can provide excellent sound insulation. An off shoot of the Palace series is the Transpalace system that allows you to have framed double glazed partitions which retains the inherent benefit of acoustics while ensuring the transparency within the room.

The President series offers single glazed partitions which can be used for variety of applications such as shop fronts, cafes, hotels, restaurants, offices where transparency and open look is of utmost importance. With its slim construction, this walls offers superior functionality and stability and can be a perfect solution for limitless creative ideas.

Project Details

Name of the project	NHIVA
Location of the project	Pune

Product Details

Palace 110 50dB CG-system Track-9 Trolley-FG4, Manual Operation
Opening Width 14,500 mm Opening Height 4,500 mm Total area 65.25 sq.m.

Wall A: 12 Standard Panels, 1 Adjusting Panels, 2 Wall Stanchions
- Wicket Panel, - Double Wicket Panel, - Passdoor
Slab/True Ceiling Height 5,500mm

Product Description

Track and Rollers: Top hung system with track and heavy duty roller system. Supplied with necessary track plates, track strips, threaded rods, nuts and washers, alignment pins etc. Tracks are supported by adjustable steel hanger brackets connected to structural support pairs of 12mm diameter threaded rods. Brackets supports the load bearing surface of the track. Track consists of natural architectural-grade aluminum alloy capable to bear the per panel load of 800 Kgs. The transfer areas are provided with aluminum junctions, switches and curves to ensure smooth transition of panels in the parking. The trolley is made of steel and provided with stainless steel rollers to ensure durability and smooth operation held with the 16mm bolt connected to the frame.

Suspension System: The ceiling track is to be fixed with an adjustable steel suspension of threaded rods. This steel suspension should be adjustable to ensure absorbtion of the eventual deflection of the ceiling. The threaded rods should be protected against corrosion.

Wall Panels: 110mm thick standard panels, filled with sound insulation materials are provided with MDF cover boards. The panels are interconnected by means of a concave / convex interlocking aluminum anodized profiles provided with an integrated EPDM magnetic strip and a vinyl acoustic seal running along the height of the interlocking profile. The skeletal frame of each element is constructed of a non-deflecting zinc coated steel tube with the aluminum anodized edge protecting profiles on both sides of the steel frame, bolted together. The cover boards are of 16mm thick MDF board, held in acoustic free suspension with the skeletal frame and within the side profiles. Each panel to have top and bottom operable EPDM pressure seals operated by a crank handle to ensure optimum contact pressure of 1500N. The system is equipped with an adjusting panel at one end of the wall. This panel normally at the closing end of the wall has a telescopic adjusting panel built with the same materials as the other panels and is operated, together with the top and bottom seals, by an internal three-way spindle mechanism. The telescopic sliding element stroke is 120 mm. There are aluminum profiles provided on both sides of the walls for better acoustics. In case of a provision of a door within the wall, the door frame jambs is provided with retractable seals for complete and tight closure of the door panel to the floor. In case of a provision of double door within the wall, there is a provision of active and inactive leaves for the door. Rrecessed door handles in satin stainless steel fininsh are provided for the doors.

MANUAL OPERATION: Each element has a spindle mechanism driven manually with the help of a bayonet connected crank handle mechanism to operate top and bottom retractable seals simultaneously.

Sonic Barrier above False Ceiling: A sonic barrier between true slab and tracks is provided above false ceiling to the true ceiling. In case of a height more than 1000mm special MS structural arrangement and sonic arrangement is provided at an extra cost in consultation with the architect / contractor.

Certification: The wall is provided with an acoustic certificate for the required sound insulation by an internationally accredited standard third party laboratory. The certification is in accordance with ISO 140-3 or EN20140.

Warranty: The system is warranted for 1 year after successful completion of the movable wall system or after 120 days of supply of material; whichever is earlier. The warranty includes normal wear and tear under normal usage and excludes any defect arising due to abuse, improper operation or insufficient maintenance and modifications executed by others.

Financial Justification

Description of Item	Quantity	Unit Rate (INR)	Total Amount (INR)
Tracks & Accessories	1	₹ 2,28,396.00	₹ 2,28,396.00
Supply of Wall A: as described under Product Details	1	₹ 18,84,057.00	₹ 18,84,057.00
Installation	Lumpsum	₹ 3,32,292.00	₹ 3,32,292.00
		TOTAL	₹ 24,44,745.00
		GST (@18%)	₹ 4,40,054.00
		GRAND TOTAL	**₹ 28,84,799.00**

Terms & Conditions:

1. The above offer is in INR (Indian Rupee) on C&F India Sea Port basis includes the following:
- Customs Duty
- Clearing & Handling
- Delivery to site
- Installation

2. Scope of work is as per below mentioned details

2.a. Supply of Tracks, Accessories & panels

2.b. Fabrication, supply and fitting of above false ceiling support structure consisting of making a frame work at 500mm - 600mm (center to center) along the main track line & 250mm - 300mm (center to center) in parking area fitted with track plates, connectors, etc. and held in position with GI steel treaded rods/bolts and double nuts	Included
2.c. Sonic Barrier above main track line consists of one layer of gypsum board on both sides dully filled in with 48-50 density of Rockwool.	Included
2.d. Installation & commissioning of tracks with fitting & alignment of panels, duly aligned and completed in full and handed over in working condition.	Included

3. The above offer does not include supply of any pocket doors.
4. The above offer excludes offloading of materials at site.
5. A suitable, safe, covered & secured Storage Area to store the materials must be arranged by you for safe storage of the partitions until installation.
6. Any I-Beams/Steel structure, wherever required, 1000mm above false ceiling shall be supplied and installed by others.
7. All electrical wiring, supply and installation of electrical sockets as required for the proper installation of the system to be supplied and installed by others.
9. All civil works, structural works, false ceiling, flooring, etc. is not included in our scope of work.
10. All necessary scaffolding, craneage, free & uninterrupted access to site & storage etc. to be provided by you.
11. The Sound insulation values quoted above are laboratory values determined in accordance with DIN EN 20140-3. Due to flanking paths in all the surrounding construction, the on site acoustic performance will be lower than the laboratory value. The on site acoustic performance of the wall is dependant on the various other aspects of construction of the room and the elements used in the room. We however recommend that the surrounding construction (ventilation ducts, cable shafts, fire fighting service, acoustic bulkhead, sound barrier above tracks, side walls, Flooring, etc.) are built to match or exceed the acoustic performance of the movable partitions. This will help to achieve an optimum acoustic performance at site.
12. Field testing is not included in our scope of work.
13. Delivery:
Tracks - 2-3 weeks from date of receipt of Purchase Order / Advance payment / Approved copy of shop drawing, whichever is later.
Panels - 8-10 weeks from date of receipt of Purchase Order / Advance payment / Approved copy of shop drawing, whichever is later.
13. Warranty: The above product is warranted for a period of 1 year from the date of delivery against any manufacturing defects.
14. Payment:
Supply - 100% advance by RTGS along with the Order.
Installation - 70% Advance along with order, 20% after track fixing and 10% after installation & handover.
15. Validity: The above offer is valid for 90 days from the date of the offer and is subject to reconfirmation. Our general terms and conditions for sales apply.

We trust our offer will meet your requirements.

If you need any clarifications/assistance, please do not hesitate to contact the us.

Assuring you of our best services at all times.

For **Hafele India Pvt. Ltd.**

I/We hereby certify that my/our Certificate of Provisional Registration GST REG-25 is in force on the date on which the Sales of the goods specified in this Bill Cash memorandum is made by me/us and that the transaction of sales covered by this Bill//Cash memorandum has been affected by me/us in the regular course of my our business

Authorized signatory