NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

YARA FERTILISER INDIA Pvt. Ltd.
Babrala 242021 Sambhal, India

Date : 12.01.2022
Quote NO : **MHE_21.22.0053**
Kind Attn : Mr. Saurabh Mathur
Email Id : saurabh.mathur@yara.com
Contact No: 9506033603

Project Name & Location: YARA FERTILISER INDIA Pvt. Ltd. Barbala Sambhal India

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation considering 03 people for 03 days per conveyor in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor** Total Length- 14.5mtr Capacity- 20-30 boxes/min	1	16,50,000	16,50,000	70,000	70,000
		Total		16,50,000		70,000
	P&F Charges	3%		49,500		70,000
	Total Without Taxes					17,69,500
2	GST Extra @ 18%	18%				Extra At Actual
3	Transportation Charges					Extra At Actual
4	Insurance Charges					Extra At Actual
5	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Empty bags lot/bundle
2	Dimension of Lot/bundle (LxBxH)	1000 mm X 700 mm X 250 mm
3	Weight of Empty Bag's lot	50 Kg
4	Capacity	20-30 boxes/min
5	Size of Belt	800 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
8	Length Of Conveyor	Fixed Length : 5500 mm Telescopic (Expanded) : 9000 mm Total : 14500 mm
9	Main Body Of Conveyor	MS Powder coated
10	Lifting Mechanism	Hydraulic power packs
11	Working height	1200 mm
12	Speed adjustment	VFD
13	Gear Box	Bonfiglioli
14	Driven Motor Make	Bonfiglioli /CG/BBL , IE2

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an adiitional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd