NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

DELICIA FOODS (Mfg.Franchisee-M/S Monginis Foods Pvt.Ltd.)
F/4, Krishna Complex, Next to Hari Har Corp. Compound,
Mankoli Naka, Post Dapode, Tal. Bhiwandi, Dist. Thane.

Project, Location :

Date : 02.03.2021
Quote NO : SQT.20.21.3053R1
Kind Attn : Sagar Mohite
Email Id : sagar.mohite@monginis.net
Contact No: 8369555945

Subject : Revised Quotation for High Speed Door - Cold Room and Dock Shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Cold Room - High Speed Doors**	4000	2500	3	325,000	975,000	15,000	45,000
2	**Retractable Dock Shelter**	3400	3400	6	59,000	354,000	10,000	60,000
	Total			**9**		**1,329,000**		**105,000**
3	P&F Charges			3%		39,870		
	Total Without Taxes					1,368,870		105,000
	GST Extra @ 18%			18%		246,396.60		18,900
	Total With Taxes					**1,615,267**		**123,900**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Retractable Dock Shelter

Sr .No.	Specification	Dock Shelter
1	**Top Curtain**	1000 mm
2	**Side Curtain**	600 mm
3	**Curtain colour**	Black
4	**Parking Guides**	White, Yellow
5	**Wall Fixings**	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
6	**Top & Side Curtains**	Double Layer High Quality Polyester
7	**Thickness**	3.0 mm
8	**Weight**	Approx 3400 g/m2

Cold Room - High Speed Doors

Designed specifically for temperature controlled rooms with both positive and negative temperatures
Curtain made of special insulated material with hidden supported windbars
Heating elements prevents ice formation even during intensive cooling.
Self-Supporting construction with anti-crash protection system for bottom profile.
Operating temperature range between +5C to -30C

Sr. No	Description	Specifications
1	Use	Internal / External Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	2,0 m/s
4	Closing speed	0,8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 1
8	Curtain	Insulated Fabric , Special 12/13 mm insulated yellow colour curtain with 3 pieces hidden windbars entegrated. Izodoor model. Thermal transmittance : 2,4 W/m2K on the curtain.
9	Guide Material	Aluminum
10	Shaft	Aluminium special drum system
11	Hood Cover	GI
12	Motor Cover	GI
13	Bottom	Flexible Rubber bottom profil system
14	Operator & Control	German Make Motor , Brakelli brand Gearmotor (with crank opening and digital enkoder) & MR220 frequency inverter drive controller 1 phase. This have 3 outputs, 8 inputs and display menu. Opening and closing variable speed adj. 0.8- 1.5 M/sn. 3 HP Gearmotor entegrated (2.2 Kw. power)
15	Connecting Voltage	230V , 1Ph , N
16	Open-Stop-Close Button	Standarad , 2 pc. mushroom buttom for opening the door
17	Protection Category	IP 65
18	Power Consumption	0.75 kw Motor
19	Emergency Off Button	Standard
20	Closing Zone Monitoring	Optical Safety edge
21	External Route Monitoring	Photocell
22	Emergency Opening	Crank Handle
23	Safety	one piece photo beam entegrates in column

NOTE: No heating system entegrated montage on + side

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd