PURCHASE ORDER

ARP CONSTRUCTION & INFRASTRUCTURE

Shop No 105, 1st floor, H-wing Jay Ganesh Samrajya Spine Road Bhosari 411039.
Email:arp.infrastructure@gmail.com Mob:9850015082,9970089098

To,
NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom,
Thermax chowk, MIDC, Chinchwad. Pune – 411019
GST TIN NO: 27AAECN0437H1ZM

Delivery Address:
John Deere India Private Limited
Gat No.166-167 & 271-291
Sanaswadi Pune 412208
GST TIN NO : 27AAACJ4233B1Z4

PURCHASE ORDER

GST TIN NO: 27AAOFA1574D1ZJ
PAN NO :AAOFA1574D
Date: 30-03-2021
P.O.NO: ARP5M003

Sr	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width	Clear Length	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Skin Rolling**	3700	4000	1	1,10,000	1,10,000	12,500	12,500
2	**Motorized Single Skin Rolling**	4000	4000	4	1,19,000	4,76,000	12,500	50,000
3	**Motorized Single Skin Rolling**	4000	5000	3	1,37,000	4,11,000	12,500	37,500
				Total		**9,97,000**		**1,00,000**
4			P&F Charges	3%		**29,910**		
			Total Without Taxes			**10,26,910**		**1,00,000**
			GST Extra @ 18%	18%		1,84,844		18,000
			Total With Taxes			**12,11,754**		**1,18,000**

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting**	Electric Motor - Indirect Mounting - Sprocket chain arrangement –
14	**Cycle per Day**	20 Cycles per Day.

TERMS AND CONDITIONS:

1)Transportation Charges In NIHVA Scope

2)Delivery: 1)Total work completed date of shed 2 & 3 will be 12/04/2021
2) Shed 1 work completed date will be 16/04/2021.

3)Payment: 1)500000/- Five lakh Advance.
2)450000/- Four lakh fifty thousand against proforma invoice.
3)76910/- Seventy six thousand nine hundred ten After material delivery within 3 days
4)100000/- One lakh of installation will be after compilation & inspection by client within 7 days.

4)Warranty: 12 months from the date of Installation

For
ARP CONSTRUCTION & INFRASTRUCTURE

Authorised Signature