NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Nutrivita Foods Pvt.Ltd
Pune

Date : 23.04.2021
Quote NO : **AS_21.22.0004**
Kind Attn : Mr. Santosh Bhandare
Email Id : santoshb@nutrivita.in
Contact No: 8888109488

Project Name & Location: Automatic Case Erector, Pune

Subject : Commercial Offer for Automatic Case Erector

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Carton Erector & Bottom Sealing** Outspeed Speed: 12 Carton /min	1	9,50,000	9,50,000	15,000	15,000
		Total		9,50,000		15,000
	P&F Charges	3%		28,500		
	Total Without Taxes			9,78,500		15,000
	GST Extra @ 18%	18%		1,76,130		2,700
	Total With Taxes			11,54,630		17,700
2	Transportation Charges			Extra At Actual		
3	Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Automatic Case Erector

Parameters	Specification
Dimensions (L x W x H)	400 x 300 x 250 mm
Height of table	Min.550mm & Max.700mm
Output Speed	12 Cartons/min
Power	Single phase, 220V/ 50/60HZ , 300W
Air Source	＞500L/min, 0.4~0.8 Mpa
Moisture	> 7-8%
Opp tape	W50mm or W60mm or W75mm
Touch screen	Simens/German
PLC	Simens/German
Cylinder	Airtac/Taiwan
Mid-relay	OMRON/Japan
Switch	Schneider/German

C) **General Conditions**

1	Installation will start after receiving of Site Readyness Photographs or written Email communication.
2	We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3	For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4	If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.
5	Once we confirm the technically & commercially clear order, we will take up the manufacture of the machine immediately in hand. Hence, we cannot accept any changes or cancellation of order and thus we cannot refund your advance amount back to you. The placing of an order with us implies acceptance of the conditions of sale here in stated regardless of any constricting clauses in the Buyers purchase order.

D) **Terms & Conditions**

Price	: Ex Works Pune.
Delivery	: 6-8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation.
Warranty	: We provide warranty of 12 months from the date of dispatch against manufacturing defects Or default workmanship. Warranty does not cover any electric or electronic parts such as AC variable drive, motor, PLC, sensor, relay etc.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd