NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0088R **Date : 22-03-2018**

Pernod Ricard India Pvt. Ltd
46, 2nd Main Rd Sampangi Rama Nagara
Sampangi Rama Nagar, Bengaluru,
Karnataka 560027

Kind Attn : Vivek Salunke
Email : vivek.salunke@pernod-ricard.com
Contact No : 7829295452

Subject : Quotation for Inclined Conveyor & Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
Option A : Inclined Conveyor (M1 + M2 + M3)					
1	**Conveyor Make - NIHVA (HSN CODE : 8428.00.00)**				
Technical Specifications	1. Conveyor Width : 500 -550mm	1	No.s	7,33,000.00	**7,33,000.00**
	2. Material To Be Handle : Boxes/ Bags				
	3. Weight Of The Box/Bags: 150 kgs				
	4. Size of Box/Bags:600 (L) x 250 (W) x 300 (H) (OVERALL)				
	5. Temperature: Ambient				
	6. Length of conveyor: 19509mm (M1 + M2 + M3)				
	7. Height of Conveyor at M1: 5400 mm				
	8. Height of Conveyor at M3: 2100 mm				
	9. Tilting Angle: 20-22 degree				
	10. Port Extension Length: 1.5 mtr at both sides				
	11. Belt type: PVC Belt				
	12. Main Body Of Conveyor: Manufacturing from MS Plate, Tube Frame Structure				
	13. Panel:The conveyor comes with a fixed main panel on rear side and front side only operating panel with emergency stopper sensor bar , LED lighting , totally consoled wiring.				
2	**Installation ,Comissioning & Training Charges**	1	No.s	80,000.00	**80,000.00**
	Total				**8,13,000.00**

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
Option B : Telescopic Conveyor (M4)					
1	**Telescopic Conveyor Make - NIHVA (HSN CODE : 84289090)**				
Technical Specifications	• Length of Conveyor : 10000 mm • Extended Length of Conveyor : 2500 + 2500 mm • Fixed Length of Conveyor : 5000 mm • Width of Conveyor : 650 mm • Material to be handle : Boxes/Cartons/Bags • Weight of Material : 35kg/each • Material of Construction : MS Painted • Loading Height From conveyor : 2350 mm • Speed Of Conveyor : 30 mtr/min Max. • Temperature : Ambient • Drive Motor • Castor Wheels For Manual Movement • Sensor and Control Panel	1	No.s	9,00,000.00	**9,00,000.00**
2	**Installation ,Comissioning & Training Charges**	1	No.s	40,000.00	**40,000.00**
	Total				

GST PUNE:	**27AAECN0437H1ZM**

Amount in Words	**Total Amount**	**17,53,000.00**
	Rupees Seventeen Lacs Fifty Three Thousand Only	

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 All structure support is in client scope
3 NIHVA Will provided structure drawing only if required
4 Existing Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra if applicable
7	**Tax**	:	GST: Extra as applicable on total supply value
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Monika Kadam
7219207333
For Nihva Technologies Pvt Ltd