NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ARWADE INFRASTRUCTURE LIMITED
Pune – 411016

Date : 30.03.2021
Quote NO : SQT.20.21.3130
Kind Attn : Sukanya
Email Id : tender@arwadeinfra.com
Contact No: 8999699306

Project, Location : Palava , New warehouse

Subject : Quotation for Rolling Shutters ,Sliding Gate ,Dock Leveler , Dock shelter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MS Motorised Rolling Shutter**	2400	3000	1	70,000	70,000	20,000	20,000
2	**Fire Rated Rolling Shutter - 4 Hrs**	2400	3000	1	235,000	235,000	20,000	20,000
3	**MS Motorised Rolling Shutter**	4000	5000	1	130,000	130,000	20,000	20,000
4	**Fire Rated Rolling Shutter - 4 Hrs**	4000	5000	1	370,000	370,000	20,000	20,000
5	**Nihva Make Dock Leveler- 15 ton**	2000	2500	1	225,000	225,000	20,000	20,000
6	**Retratable Dock Shelter**	3400	3500	1	80,000	80,000	10,000	10,000
7	**Automatic Sliding Gate**	9000	1800	1	290,000	290,000	20,000	20,000
8	**Automatic Sliding Gate**	6000	1800	1	250,000	250,000	20,000	20,000
9	**Manual Wicket Gate**	1500	1500	1	30,000	30,000	10,000	10,000
	Total			**9**		**1,680,000**		**160,000**
10	P&F Charges			3%		50,400		
	Total Without Taxes					**1,730,400**		**160,000**
	GST Extra @ 18%			18%		311,472.00		28,800
	Total With Taxes					**2,041,872**		**188,800**
11	Transportation Charges					**Extra at atcual**		
12	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MS Motorised Rolling Shutter

Sr .No.	Specification	MS Motorised Rolling Shutter
1	**Description:**	MS Motorised Rolling Shutter with MS Laths with thickness of 1.2 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.2 mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -As per the opening width dimension
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	2 coat of enamel paints.
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Fire Rated Rolling Shutter

2 Hrs & 4 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED
- **Shutter Slats: SKB-A7 Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: G-65 GI Guide Rail**
- **Operated by: Motor with one unit push button switch & manual override**





Sr .No.	Specification	2 Hour Fire Rated Rolling Shutter
1	Certification	BS 476 Part 22 & MS 1073 Part 3 1988 Tested in Warrington Fire Reasearch Centre UK & Sirim Malasiya
2	Test	UL - 10B Tested
3	Shutter Slats	Zinc coated steel solid slats
4	Shutter Curtain	Roll formed from 1st grade BHP Zincalume steel SKB-A7 curve slat curtain
5	Guide Rail	Fabricated from hot-dipped galvanised steel of 3.0 mm with one piece design surface mounted type.
6	Bottom Bar	SKB- T-120 Assembled of 2 Pieces of 38 x 38 x 3 mm galvanised steel angle bolted 800 mm pitch with galvanised bolts and nuts or 2 pieces of 40 x 40 x 6 mm steel flat bar.
7	Shutter Enclosure Box	Pressed Galvanised steel sheet to suite box size comply to fire test approved thickness.
8	Operation Control	Gear motor with Thermal protector, limit switches, manual overide, c/w push button switch with keys lockable.
9	Motor Drive Unit	Power Source: 230v 50Hz 1 phase Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
10	Fire Mode	Fire Shutter will auto close via upon receiving of 24VDC fire signal

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Nihva Make Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	15 Ton UDL
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
9	Lip size (W x L)	2000 x 400 mm
10	Shut Height	480 mm
11	Maximum slope can be achieved	0.1
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
14	Hydraulic power pack	Standard
15	Driver type	Direct by electric Motor
16	Motor Ratings	1 H.P
17	Pump design flow	2.5 LPM
18	Pump pressure	120 bar Operating 200 bar Max.
19	Safety valve set pressure	120 Kg/cm²
20	Pump Type	Gear
21	Volume of oil receiver	7 Lit
22	No Of Deck cylinder	2 No
23	Lip Cylinder	1 No

Rectratable Dock Shelter



Sr. No	Description	Specification
1	Size	(W) 3400 mm x (H) 3500 mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
5	Curtain colour	Black
6	Parking Guides	White, Yellow
7	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
8	Top & Side Curtaiins	Double Layer High Quality Polyester
9	Thickness	3.0 mm
10	Weight	Approx 3400 g/m2

Automatic Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	80 x 80 x 3.2mm MS SQ. TUBE
6	For Post	80 x 80 x 3.2mm MS SQ. TUBE
7	Innear Tube	32 x 32 x 2.6 mm MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5-6 weeks for Dock Leveler , Dock Shelter & rolling shutter , 8-9 Weeks for Sliding Gate & Fire rated Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd