NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

LEAN AUTOMATION EQUIPMENTS PVT. LTD.
GUT No 212/2, Chakan Talegaon Road,
Village Mahalunge (Ingle),
Chakan, Pune – 410501

Date : 27.01.2020
Quote NO : SQT/19-20/2260R5
Kind Attn : Mr. Praveen Kedarji
Email Id : praveen.kedarji@leanautomation.in
Contact No: 9028765807

Subject : Quotation for High Speed Door RP300.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany make Machine Protection Door RP300 - Including 24 Months Warranty.**	3200	2500	1	6,85,000	6,85,000	-	-
2	**Supporting Structure Required for Door Mounting**	**In client Scope**				-		-
3	**Installation of Door at czech republic**			1			90,000	90,000
				Total		**6,85,000**		**90,000**
4	P&F Charges				Nil			
	Total Without Taxes				6,85,000		90,000	
	GST Extra @ 18%			18%	1,23,300.00		16,200	
	Total With Taxes				**8,08,300**		**1,06,200**	
5	Transportation Charges				In NIHVA Scope			
6	Unloading Charges @ Site				In Client Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Details
		Albany make Machine Protection Door RP300
1	Door version:	**Vertical Rapid Roller Door for machine protection.**
2	Side Frames:	**Aluminum anodized two parts, to have easy access to switches and service.**
3	Door blade:	**PVC material transparent with reinforcement stripes silicone-free in blue (similar RAL 5010).**
4	Bottom beam	**Aluminium anodized.**
5	Drive unit:	**Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)**
6	Opening / closing speed:	**Approx. max. 2,0 / 1,2 m/s**
7	Control system:	**MCC Vector Control**
8	Power suppy:	**3/(N)/PE 230/380/400/415 V, 50 Hz**
9	Safety features:	**Safety edge with cable chain integrated in side frames, pre running photocell.**
10	Safety limit switch:	**1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : AT SITE Lean Automation Chakan Pune

Delivery : 13 - 14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment Supply : 50% Advance along with Confirmed Purchase Order & Balance 50% against door arival at NHAVA SHEVA port Mumbai

Installation : 100 % After Installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 24 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd