NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

D. Y. Patil stadium
Navi Mumbai ,
Sector 7

Date : 11.09.2019
Quote NO : SQT/19-20/1999R
Kind Attn : Mr.Vijay Chougale
Email Id : vijaydyp.chougale@gmail.com
Contact No: 9768066968

Subject : Quotation for Boom Barrier and Bollards.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Diameter (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Boom Barrier (Length 6 Mtr)			8	1,40,000	11,20,000	20,000	1,60,000
2	Bollard - STOPY B (Option - 1)	200	700	11	2,28,000	25,08,000	20,000	2,20,000
3	Bollard - K12 (Option - 2)	330	1200	11	14,12,000	1,55,32,000	20,000	2,20,000
4	Bollard - K4 (Option - 3)	275	800	11	9,43,000	1,03,73,000	20,000	2,20,000
				Total				**3,80,000**
5	P&F Charges			3%		-		
	Total Without Taxes					-		3,80,000
	GST Extra @ 18%			18%		-		68,400
	Total With Taxes					**-**		**4,48,400**
6	Transportation Charges					In Client Scope		
7	Unloading Charges @ Site					In Client Scope		
	ACCESSORIES							
8	Control Unit for Bollard - STOPY B (1 Controller Can Operate 4 Bollards)			1	32000	32000		
9	Control Unit for Bollard - K12 and K4 (1 Controller Can Operate 2 Bollards)			1	30000	30000		
10	RME 2 dual channel metal object detector			1	17000	17000		
11	ACOUSTIC DETECTOR			1	425000	425000		
12	Hydraulic unit for XPASS B 330/1200			1	30000	30000		
13	Battery module for EFO.			1	45000	45000		
14	Manual pump with 2 litre tank for hydraulic bollards			1	60000	60000		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

BOOM BARRIER
Each Boom Barrier Set include: **MICHELANGELO BT A Barrier-1No.** **• Round Boom First part-1No.** **• Round Boom Second part- 1 No.** **• Anchor Base- 1No.** **• MOB. Boom Rest-1No.** **• Rubber Safety Profile- 1No.** **• OMEGA AT Acce. - 1No.** **• Transmitter with Channels- 1No.** **• Push Button/Remote**
STOPPY B Bollards
Automatic Electromechanical bollard. **• diameter 200 mm and height 700 mm.** **• Control unit - Can manage up to 4 bollards at the same time** **• Push Button.**
hydraulic bollard K12
Automatic Electromechanical bollard. **• diameter 330 mm and height 1200 mm.** **• Control unit - Can manage up to 2 bollards at the same time** **• Push Button.**
K4 rated Bollard
Automatic Electromechanical bollard. **• diameter 275 mm and height 800 mm.** **• Control unit - Can manage up to 2 bollards at the same time** **• Push Button.**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat on 7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd