NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

NIHVA Sales Quotation

Eco Clean Machines Pvt. Ltd.
Plot No. A57/58, H Block, MIDC Pimpri
411018 Pune

Date : 09.02.2021
Quote NO : SQT_20.21.2449R
Kind Attn : Amruta Dhanurkar
Email Id : purchase.india@ecoclean-group.ne
Contact No: 7820860618

Project Name & Location: Pune

Subject : Quotation for Hand Operated Siccor Lift Trolley with Roller on Top

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR	
		(Nos)	Unit Price	Total Amount
1	**Hand Operated Siccor Lift Trolley with Roller on Top**	1	1,12,500	1,12,500
2	**Irrection And Comissioning for Pune Location**	1	5,000	5,000
		Total		**1,17,500**
3	P&F Charges on Total Supply Value	3%		**3,375**
	Total Without Taxes			**1,20,875**
	GST Extra @ 18%	18%		**21,150**
	Total With Taxes			**1,42,025**
4	Transportation Charges			**Extra At Actual**
5	Unloading Charges @ Site			**Extra At Actual**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

B) Technical Specification -

Hand Operated Siccor Lift Trolley with Roller on Top

Sr. No	Description	Specifications
1	Capacity	150 Kg
2	Platform size	800 x 600 mm
3	Shut Height	350 mm
4	Max Height	1250 mm
5	Lift Height	900 mm
6	HAND PUMP	DOWTY/LOCAL MAKE 3 LTR TANK



NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 6-8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with purchase order and 20 against material dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat 7410169333**

With Best Regards
Prtaibha Mete
8530872333
For NIHVA Technologies Pvt Ltd