NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Crane Process Flow Technology Pvt Ltd
Satara

Date : 20.10.2020
Quote NO : SQT.20.21.2747R1
Kind Attn : Abdul Chinchanikar
Email Id : projectsupport@wanigroup.com
Contact No: 8149707826

Project Name & Location: Satara

Subject : Quotation for Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	3500	3600	1	116,000	116,000	20,000	20,000
2	Motorized Rolling Shutter	3000	3200	2	100,000	200,000	20,000	40,000
3	Motorized Rolling Shutter	4000	3000	1	110,000	110,000	20,000	20,000
4	Motorized Rolling Shutter	3000	3000	5	98,000	490,000	20,000	100,000
5	Motorized Rolling Shutter with Grill	3000	3000	1	100,000	100,000	20,000	20,000
6	NIHVA Sectional Doors (Vertical Lift)	3000	3000	1	200,000	200,000	20,000	20,000
7	NIHVA Sectional Doors (Vertical Lift)	4000	3000	1	221,000	221,000	20,000	20,000
8	NIHVA High Speed Doors	3000	3000	1	250,000	250,000	20,000	20,000
9	NIHVA High Speed Doors	4000	3000	1	280,000	280,000	20,000	20,000
10	Automatic Sliding Gate	12000	1500	1	470,000	470,000	20,000	20,000
11	Automatic Sliding Gate	10000	1500	1	450,000	450,000	20,000	20,000
12	Wicket Gate	1200	1200	1	30,000	30,000	10,000	10,000
13	Wicket Gate	1000	1350	1	25,000	25,000	10,000	10,000
14	Boom Barrier		5000	6	110,000	660,000	20,000	120,000
15	Boom Barrier		4000	6	110,000	660,000	20,000	120,000
				Total		**4,262,000**		**580,000**
16	P&F Charges			3%		**127,860**		
	Total Without Taxes					**4,389,860**		**580,000**
	GST Extra @ 18%			18%		790,175		104,400
	Total With Taxes					**5,180,035**		**684,400**
17	Transportation Charges					**In Client Scope**		
18	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter with Grill

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Honeycomb Grill**	600mm grill at 3000mm height from Bottom.
14	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Sectional Door Vertical Lift

Sr. No	Description	Specification
1	**Opening Direction & Mounting**	Standard (Vertical)
2	**Opening/Closing Speed**	CDM9 0,28 m/s
3	**Door Material**	Steel
4	**Panel Thickness**	42 mm Square Grid, steel sheet
5	**Filling**	CFC-free polyurethane
6	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
7	**Water Penetration**	EN 12425 class 3
8	**Air Permealibity**	EN12426 class 3
9	**Thermal Transittance**	EN 12428 1.10W /m2K
10	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
11	**Door saftey**	Doors equiped with spring break device
12	**Incase of Power failuer**	Doors to be equiped with quick release fuction
13	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
14	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
15	**Emergency Operation**	by Disengagement rope manual
16	**Operating Switch**	Up/Down Keypad + stopbutton
17	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
18	**Environmental Green Product**	As per ISO 14025 and EN 15804

High Speed Door

Sr. No	Description	Specification
1	**Construction:**	High-Speed Roller Door with transparent curtain and reinforcement stripes according to the following RAL
2	**Side frames:**	Side frames galvanized, bottom rail profile made of aluminium
3	**Drive Unit:**	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
4	**Control system :**	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down button.
5	**Power supply:**	3/(N)/PE/230/400/415 V, 50 Hz.
6	**Safety features:**	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and mechanical

Motorized Sliding Gate

Sr .No.	Specification	Motorized Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	100 X 50 X 4 mm THK SQ. TUBE
6	**For Post**	100 X 50 X 4 mm THK SQ. TUBE
7	**Inner Vertical Flat**	50 X 10 mm FLAT
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

Boom Barrier

Sr .No.	Description	Specifications
1	**Size**	4 meter / 5 meter
3	**Opening time**	3S
4	**Motor Power Supply**	24V
5	**Type of limit Switch**	Electronic
6	**Safety**	Photocell sensor, Flashing Light With Buzzer
7	**Operated**	Push Button Pedant

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd