**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Date : 21.11.2020**
Quote NO : SQT.20.21.2838

**PSR Projects**
**Hyderabad**

**Kind Attn : P satyam Reddy**
Email Id : psrprojects1234@gmail.com
Contact No : 9618245700

**Project Name & Location: Hyderabad**

**Subject : Quotation for Sectional Door,Sliding Gate, Boom Barrier etc.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 4 |

**A)** Commercial Offer

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Sectional Doors - Vertical Lift** | 4800 | 3100 | 1 | 361,178 | 361,178 | 20,000 | 20,000 |
| 2 | **Sectional Doors - Vertical Lift** | 3000 | 3200 | 1 | 290,119 | 290,119 | 20,000 | 20,000 |
| 3 | **Motorised Sliding Gate** | 5500 | 1800 | 1 | 332,000 | 332,000 | 20,000 | 20,000 |
| 4 | **Boom Barrier - 6 Mtr with access card** | | | 2 | 140,000 | 280,000 | 15,000 | 30,000 |
| | | | | **Total** | | **1,263,297** | | **90,000** |
| 5 | P&F Charges | | | 3% | | **37,899** | | |
| | **Total Without Taxes** | | | | | **1,301,196** | | **90,000** |
| | GST Extra @ 18% | | | 18% | | 234,215 | | 16,200 |
| | **Total With Taxes** | | | | | **1,535,411** | | **106,200** |
| 6 | Transportation Charges | | | | | **Extra at actual** | | |
| 7 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**ASSA ABLOY Motorised Sectional Doors**





| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Model No | ASSA ABLOY OH1042P |
| 2 | Opening Direction & Mounting | Vertical |
| 3 | Opening/Closing Speed | CDM9 0,28 m/s |
| 4 | Door Material | Steel |
| 5 | Panel Thickness | 42 mm Square Grid, steel sheet |
| 6 | Filling | CFC-free polyurethane |
| 7 | Door sealent | All door sealants made of EPDM rubber, temperature resistant -30/+70 |
| 8 | Water Penetration | EN 12425 class 3 |
| 9 | Air Permealibity | EN12426 class 3 |
| 10 | Thermal Transittance | EN 12428 1.10W /m2K |
| 11 | Bottom sealing | Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM |
| 12 | Door saftey | Doors equiped with spring break device; Safety Photo cell, bottom safety edge, rope |
| 13 | Incase of Power failure | Doors to be equiped with quick release fuction |
| 14 | Operator power conumption | Operator to have a maximum power consumption of 0,37kW and a standby |
| 15 | Drive Unit & Mounting Type | Single phase 230V direct drive on shaft |
| 16 | Emergency Operation | by Disengagement rope manual |
| 17 | Operating Switch | Up/Down Keypad + stopbutton |
| 18 | Locks : Lock bolt | The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is |
| 19 | Environmental Green Product | As per ISO 14025 and EN 15804 |
| | | |
| | | |
| | | |
| | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

| **Boom Barrier** | | |
|---|---|---|
| | | |
| Sr. No. | **Description** | **Specifications** |
| 1 | Size | 6 Meter |
| 2 | Model No | Michealangelo 60 |
| 3 | Opening Time | 6 S |
| 4 | Slowdown | Adjustable |
| 5 | Motor Power Supply | 24 V |
| 6 | Type of limit Switch | Electronic |
| 7 | Frequency of Use | Continuous Use |
| 8 | Protection Rating | IP54 |
| 9 | Lock | Mechanical |

**Motorised Single Leaf Sliding Gate**

| Sr. No. | **Description** | **Specifications** |
|---|---|---|
| 1 | Opening Direction | Horizontal - from left to right or reverse |
| 2 | Mounting Location area | Inside area |
| 3 | Design Pattern | Standard Tubular Design Pattern |
| 4 | OUTER TUBE | 72 x 72 x 3.2mm MS SQ. TUBE |
| 5 | FOR POST | 72 x 72 x 3.2mm MS SQ. TUBE |
| 6 | INNEAR TUBE | 38x38x3.20mm/40x40x3.2 MS SQ. TUBE |
| 7 | Gap Between Tubes | 125mm |
| 8 | Bottom Rail on ground | Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 9 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| 10 | Guide Rollers supporter during Gate | Nylon Rollers with Bearings both side mounted on column for support smooth |
| 11 | Painting | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| 12 | El motor make | BFT – Italy (100% imported) |
| 13 | Emergency Operation | Manual after turn the switch |
| 14 | Operating Switch | Push Button from inside |
| 15 | Safety | Photocells, Flashing Light |
| | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2008 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C)** General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note:** **Please find below List which are in Client Scope**

| Sr. No | **Description** |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil structural work required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D)** Terms & Conditions

| | |
|---|---|
| Price | : Ex Works Pune |
| Delivery | : 1) For Sectional Doors 12-14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.<br>2) For Sliding Gate and Boom Barrier 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval |
| Payment | : 80% Advance along with Confirmed Purchase Order & Balance against readyness of material before dispatch. |
| Validity | : Validity of Offer is 15 days from the date of quotation |
| Warranty | : 12 months from the date of supply. |

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bikash Sahu on 8530926333.**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd