WORK ORDER

Client
ABB India Limited

PO Number:		5191320793	W. O. no-	SO/20-21/114
PO Dated :		09-Feb-21	W. O. Date	09-Feb-21
PO Received Date:		09-Feb-21	Sales Co ordinator	Shailesh Bhoir
Ref. Quotation:		SQT.20.21.3003R	Front Sales Person	Shrikant Mirkute

Dispatch Address:

Plot No. 5 & 6, 2nd Stage, Peenya Industrial Area IV, Peenya, Bengaluru 560058, Karnataka - India

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply	Installation	Amount	Dwg. Approval
1	RP300_4000 X 2500 ASSA ABLOY Machine Protection Door - RP3		NOS	2		Inclusive	-	Pending
		Total		2			-	

Sr. No	Description	Details
1	Door version:	Vertical Rapid Roller Door for machine protection.
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	Rolltex Plus Curtain with RAL Blue 5002
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Opening / closing speed:	Approx. max. 2,4 / 1,7 m/s
7	Control system:	MCC Vector Control
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	pre running photocell.
9	Photocell	with Photocell
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	Window Type	700 x 500 mm Anti UV Type
12	Window Qty	1 No

A) Commerical Terms

1)	**Payment Terms:**	100% After delivery(30 days end of month after invoice date)
2)	**Delivery Date as per PO:**	23.03.2021 - Delivery : 5 weeks = 4 weeks mfg + 1 week air transport
3)	**Transportation:**	Inclusive (AIR Frieght Charges)
4)	**P&F Charges:**	NIL
5)	**Loading:**	NIHVA
6)	**Unloading:**	In Client Scope
7)	**Lifting Equipments:**	NIHVA
8)	**Warranty:**	12 Months from date of Supply
9)	**Height arrangement:**	NA
10)	**Electricity Supply:**	Client
11)	**GST:**	18% Extra
12)	**Installation Scope:**	NIHVA
13)	**Mode of import:**	NA
14)	**HSS:**	NA
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT		PPC	DESIGN	Date & Time
A. K.	S.M.					