Client : Nihva Technologies Pvt Ltd.

Project : New

Encl to our letter no : RPFS/QTN/RP/Jan/11/12/01/2024

Supply of **`Radiant Passive' HMPS** Door hinge type with shutter designed and manufactured from 0.8 mm thick GI sheet duly affixed with internal stiffeners to mount accessories and internally insulated with Honey Comb and panel having overall thickness of 40 mm. The frame is fabricated from 1.2 mm thick GI sheet having single rebate having profile size of 100 x 57 mm with necessary stiffeners and duly treated with zinc etch primer with coating of surfacer and final finish of powder coating as asked in the technical specifications.

Sr. No.	Door Description	Grid No.		Door TYPE	SIZE Req.		Thickness	Material		Wall Thickness	Wall Type	Rate	Total
		From	To		L	W		Inner Side	Outer Side				
A.	**DISPATCH AREA ANTE ROOM**												
1	D2	A'-1	A-2	HMPS	900	2200	40	PPGI	PPGI	150 mm	BRICKWALL	18,810.00	18,810.00
2	D2	A'-4	A-5	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
B.	**GENTS AND LADIESCHANGE ROOM**												
1	D	B-4	C-5	HMPS	1000	2200	40	PPGI	PPGI	150 mm	BRICKWALL	20,900.00	20,900.00
2	D	B-4	C-5	HMPS	1000	2200	40	PPGI	PPGI	150 mm	BRICKWALL	20,900.00	20,900.00
3	D	B-4	C-5	HMPS	1000	2200	40	PPGI	PPGI	150 mm	BRICKWALL	20,900.00	20,900.00
4	D	B-4	C-5	HMPS	1000	2200	40	PPGI	PPGI	150 mm	BRICKWALL	20,900.00	20,900.00
5	D	B-4	C-5	HMPS	1000	2200	40	PPGI	PPGI	150 mm	BRICKWALL	20,900.00	20,900.00
C.	**ANTE ROOM/2.9M WIDE CORRIDOR**												
1	D1	B-4	C-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
2	D1	C-4	C-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
3	D1	C-5	D-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
4	D1	D-5	E-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
5	D1	E-5	F-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
6	D1	E-4	F-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
7	D1	E-4	F-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
8	D1	E-4	F-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
9	D1	E-4	F-5	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
D.	**CONTROL ROOM, SMP DAY STORE AND CURD PROCESSING SECTION**												
1	SD	A-5	B-6	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
2	SD	B-5	B-6	HMPS	1500	2200	40	PPGI	PPGI	150 mm	BRICKWALL	31,350.00	31,350.00
3	SD	A-6	B-7	HMPS	1500	2200	40	PPGI	PPGI	230 mm	BRICKWALL	31,350.00	31,350.00
4	D1	A-7	B-7	HMPS	1500	2400	40	PPGI	PPGI	230 mm	BRICKWALL	34,200.00	34,200.00
E.	**HOT WATER DIPPING ROOM AND PANEER PROCESSING SECTION**												
1	D1	D-5	E-6	HMPS	1500	2400	40	PPGI	PPGI	150 mm	BRICKWALL	34,200.00	34,200.00
2	D1	E-5	E-6	HMPS	1500	2400	40	PPGI	PPGI	150 mm	BRICKWALL	34,200.00	34,200.00

Sr. No.	Door Description	Grid No.		Door TYPE	SIZE Req.		Thickness	Material		Wall Thickness	Wall Type	Rate	Total
		From	To		L	W		Inner Side	Outer Side				
A.	**ELECTRICAL PANEL ROOM, BOILER ROOM & BRIQUETTE STORE ROOM**												
1	RS	A-1	A-2	GI	2500	3000				230 mm	BRICKWALL	71,250.00	71,250.00
2	D	A-1	A-2	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
3	ED	C-1	C-2	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
4	RS	A-2	A-3	GI	3000	3000				230 mm	BRICKWALL	85,500.00	85,500.00
5	RS	A-3	A-4	GI	3000	3000				230 mm	BRICKWALL	85,500.00	85,500.00
6	D	A-3	A-4	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
7	ED	C-3	C-4	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
8	RS	A-4	A-5	GI	3000	3000				230 mm	BRICKWALL	85,500.00	85,500.00
9	ED	C-4	C-5	HMPS	900	2200	40	PPGI	PPGI	230 mm	BRICKWALL	18,810.00	18,810.00
												Basic Total…Rs.	**10,42,720.00**
												Add. GST @ 18 %...Rs.	**1,87,689.60**
												Total Amount…Rs.	**12,30,409.60**

Terms & Condition

Note: **Rate includes with standard accessories,Packing and installation charges. Any change in Accessories / hardware's make, would impact the prices given.**

Price: EX works Ahmedabad.

Payment : 50 % advance along with the order, 50 % against inspection and prior to dispatch of the material at our premises.

Freight : Extra At Actual.

Delivery :	03-04 weeks from the date of receipt of your technically and commercially clear purchase order including drawings duly approved from your end (likely to vary depending upon the order quantity), subject to force majeure conditions.
Unloading & Storage :	Kindly note that once the material reaches at site you will accommodate for unloading of the material and proper storage of the same at site. Lifting and shifting of doors from stores to respective door openings at site will be done by you, which please note.
Scope of Installation :	We will depute our supervisor at site and you will provide with necessary team comprising of skilled & unskilled manpower for installation and our supervisor will co ordinate with the said team for smooth installation of these doors.
Warranty :	12 months from the date of installation or 13 months from the date of dispatch, whichever earlier.
Validity :	30 days and subject to confirmation thereafter.

For RADIANT PASSIVE FIRE SYSTEMS

MITESH CHOKSHI - PARTNER
MOB: +91 93274 30813 / +91 98793 17938