NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom,
Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Dell'Orto India Pvt Ltd
Chakan, Pune - 560105

Date : 18.10.2021
Quote NO : AS_21.22.0040
Kind Attn : Mr. Bhupen Dorle
Email Id : Bhupen.Dorle@dellorto.it
Contact No: 9850241110

Project Name & Location: Dell'Orto India Pvt Ltd, Chakan Pune

Subject : Commercial Offer for Pit Monuted Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Monuted Hydraulic Scissor Lift** • Capacity 2 Ton • Lifting Height -1800 mm • With Bellows	1400 W mm X 2100 L mm	1	4,12,500	4,12,500	15,000	15,000
2	**Pit Monuted Hydraulic Scissor Lift** • Capacity 2 Ton • Lifting Height-1200 mm • Without Bellows no beam detector	1400 W mm X 2100 L mm	2	2,87,500	5,75,000	15,000	30,000
3	**Pit Monuted Hydraulic Scissor Lift** • Capacity 2 Ton • Lifting Height- 1800 mm • With Bellows	1400 W mm X 1400 L mm	2	4,00,000	8,00,000	15,000	30,000
			Total		**17,87,500**		**75,000**
		P&F Charges on Total Supply Value	3%		**53,625**		
		Total Without Taxes			**17,87,500**		**75,000**
4	GST Extra @ 18%						**Extra At Actual**
5	Transportation Charges						**Extra At Actual**
6	Unloading Charges @ Site						**In Client Scope**
7	**Only Lift table bellow**						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Pit Monuted Hydraulic Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	2 Ton
2	**Platform size in mm**	1400(W) x 2100 (L) and 1400(W) x 1400 (L)
3	**Shut Height**	600 mm
4	**Max ht**	1800 mm and 2400 mm
5	**Lift ht**	1200 mm and 1800 mm
6	**Safety Railing**	Both length side only (900 mm height)
7	**Color**	As per req. RAL shade.
8	**Lip**	Manual Lip on one side
9	**Hyd Cylider - Seal kit (Rod end , Head end & Piston)**	Standard
10	**Hydraulic power pack**	3HP, 3 Phase
11	**Ele. Motor**	Siemens / Equivalent

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact Mr.Vijay Tarak on 8551093333.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd