NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Finearc Systems Pvt. Ltd
21, F-2 Block, MIDC, Pimpri
Pune - 411018

Project, Location :

Date : 15.03.2021
Quote NO : SQT.20.21.3104
Kind Attn : M.P.Athavale
Email Id : purchase2@finearcsystems.com
Contact No: 8888828208

Subject : Quotation for Machine Protection Door - RP 300 - High Sea Sales

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer - -without custom duty + clearnce + Local transport - HIGH SEA SALES - BY SEA

Sr No	Description	Size		Qty	Supply Charges in INR (High Sea Sales)		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany make Machine Protection Door - RP 300**	4000	2500	1	733,000	733,000	20,000	20,000
	Total			**1**		**733,000**		**20,000**
2	P&F Charges			0%		-		
	Total Without Taxes					733,000		20,000
	GST Extra @ 18%			18%		131,940.00		3,600
	Total With Taxes					**864,940**		**23,600**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Albany make Machine Protection Door RP300

Sr. No	Description	Albany make Machine Protection Door RP300
1	Door version:	Vertical Rapid Roller Door for machine protection.
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	Rolltex Plus Curtain
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Opening / closing speed:	Approx. max. 2,4 / 1,7 m/s
7	Control system:	MCC Vector Control
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	Safety edge with cable chain integrated in side frames, pre running photocell.
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	Window Type	700 x 500 mm Anti UV Type
12	Window Qty	1 No
13	Motor & Hood Cover	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd