NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1436R **Date : 10.04.2019**

CNH Industrial (India) Pvt. Ltd.
A-1/1, Chakan Industrial Area,
Phase-II, Village- Shinde,
Tal.–Khed, Pune–410501,

Kind Attention : Mr. K.N. Pandey
Email ID : k.pandey@cnhind.com
Contact No : 9711333327

Project Name And Location : CNH Industrial (India) Pvt. Ltd.
Subject : Motorised Rolling Shutter

Dear Sir

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorised Rolling Shutter**				
A	**Technical Details :** **• Opening Direction: Vertical - from bottom to Top ; Mounting Location area : Inside area** **• Mounting Surfacer : Side Brackets: Optional Guides : Optional** **• Curtain material : MS ; Curtain Profile : Curved** **• Curtain Panel: The panel made of 1.0mm GI Steel** **• Slat Thickness : 1 mm (As per IS 6248)** **• Side Guide Profile : M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)** **• Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h** **• Side Brackets : MS Plate 3 mm to 10 mm thick , as per the opening dimension** **• Hood Cover : Made of GI Sheet Thickness 0.8 mm with 25x25x3mm angle stiffener** **• Painting : 2 Coats of Epoxy primer and 2 coats synthetic enamel** **• Control Type: Optional = Dead man / Pulse Control** **• Drive Unit & Mounting Type : Electric Motor (Imported China make) (single phase / three phase) - Indirect Mounting - Sprocket chain arrangement** **• Emergency Operation : Option = Manual Hand Driven ; Operating Switch : Option = Push Button from inside** **• Installation Constraint any : Need to be check = space requirements + substructure + Mounting access + Access in the event of power cut.** **• Weight = 25Kg / m2** **• Technical Specification Of Motor :** **1. Torque = 809 N.m ; 2. Voltage = 430 V ; 3. Power = 780 W** **• Safety feature :** **Dedman Control Switch; Simple Manual Operation in case of powre cut.**				
1	Size : (W)6000 mm x (H)6000 mm (Supply + Installation+ Scaffolding)	2	No	247,000	494,000
2	Size : (W)5000 mm x (H)5000 mm (Supply + Installation + Scaffolding)	6	No	179,000	1,074,000
3	Removing the Existing shutter	8	No	20,000	160,000
	Total				**1,728,000**

GST Pune	**27AAECN0437H1ZM**

Total	**1,728,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18% Extra
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification in this concern

With Best Regards

Ulka Auti

7219206333

For Nihva Technologies Pvt Ltd