**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Flipkart Internet Pvt Ltd**
Tower C, Ground floor, Embassy Tech Village
Devarabeesanahalli ,Bangalore - 560103

**Date :** 15.03.2021
**Quote NO :** **AS_20.21.0016**
**Kind Attn :** Mr. Palvannan Krishnan
**Email Id :** k.palvannan@flipkart.com
**Contact No:** 9620811725

**Project Name & Location: Telescopic Belt Conveyor, Bangalore**

**Subject : Quotation for Telescopic Belt Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Conditions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | | Installation consodering 03 people for 03 days per conveyor in INR | |
|---|---|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Telescopic Belt Conveyor ( 5 mtr fixed and 10 mtr extended)** **Note: This Price is for min. qty of 25 Nos.** | 1 | 16,50,000 | 16,50,000 | 75,000 | 75,000 |
| | **Total** | | 16,50,000 | | | 75,000 |
| 2 | P&F Charges | | 25,000 | | | |
| | Total Without Including Taxes | | 16,75,000 | | | 75,000 |
| | GST Extra @ 18% | 18% | 3,01,500 | | | 13,500 |
| | Total Amount Including Taxes | | 19,76,500 | | | 88,500 |
| 3 | Transportation Charges | | **Extra At Actual** | | | |
| 4 | Unloading Charges @ Site | | **In client Scope** | | | |

**Note: If you require extra people at the time of installation, will cost you extra.**

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Telescopic Belt Conveyor**

| Parameters | Specification |
|---|---|
| Total length of conveyor | 15000 mm |
| Collapsed length | 5000 mm |
| Telescopic Length | 10000 mm |
| Width Of Conveyor Belt | 800 mm |
| Conveyor Capacity | 50 kg/mtr |
| Speed | 30 mtr / min ( Variable speed) |
| Drive Type | VFD |
| Conveying | Auto/ Manual |
| Telescopic | Auto/ Manual |
| Lifting Support | Through Hydraillic |
| For Detailed Specifications | Please Refer Annexture |

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**D) Terms & Conditions**

**Price** : Ex Works Pune.

**Delivery** : Discuss at the time of commercial discussion, Advance Payment & Drawing approval.

**Payment** : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak 8551093333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd