Daccess Security Systems Pvt ltd
Revati Arcade 2, Office No 5.
3rd floor baner ,pune
Pune, Maharashtra 411045
Tel. No: 02041241256
Email id-info@daccess.co
WWW.daccess.co.in

Full Height and Half Height Turnstile Gate

To		Quot No	DA#21211-1	
	NIHVA Technology Pvt Ltd,	Quot Date	11/02/21	
	Kind Attention- Mr Vijay Tarak	GST No		

No.	Description	Rate in INR	Qty.	Amount in INR
1	**Single Lane Full Height Turnstile Gate: SS 304** • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. nlock time: 0.2s Pass rate: 30 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w Weight:220kg	220000.00	1	220000.00
	OR			

2	**Single Lane Half Height Turnstile Gate: SS 304** • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatically in certain time, and the potency is small, will make an alarm sound at the same time. • Reseng automatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. nlock time: 0.2s Pass rate: 35 person/min each from both gates; Pass Width: 550mm ; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w Weight: 45kg **Make : Entero Model : ENT 121**	**40000.00**	**1**	**40000.00**
3	**Fastner and hardware for Fitting of Full height turnstile.**	**4500.00**	**1**	**4500.00**
4	**Smart card reader**	**2850.00**	**2**	**5700.00**
5	**Controller for entrance system with SMPS power supply**	**18000.00**	**1**	**18000.00**
			Project Cost	**288200.00**
			Installation, Testing & Commisioning along with 1 year service support	**your scope**
			Transportation cost	**extra**
			Total Project Cost	
	Optional Device			
1	**Finger print attendance system + card reader**	**14500.00**	**2.00**	**29000.00**
2	**Face + Finger print attendance system + card reader**	**22500.00**	**2.00**	**45000.00**
			Total Cost	**74000.00**
	Terms & Conditions:			
1	**GST : 18% Extra at actual.**			
2	Warranty : 1 year warranty for supplied material, from the date of delivery on site.			
3	Client Scope : Cabling, digging & civil work. Installation work.			
4	Payment Schedule : 100% Advance with PO.			

5	Delivery : 3-4 weeks.
6	**Transportation : Client Scope/ At Actual**
	Expecting your Positive response. We will Please Serve Our Best
	Dhananjay Sonawane (9370299634)