NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Goa Shipyard Limited
Goa

Date : 20.07.2023
Quote NO : RR_23.24.0074
Kind Attn : Mr. Vijaya Kumar Bandri
Email Id : bvijayakumar@goashipyard.com
Contact No: 9423323208

Project Name & Location: Goa Shipyard Limited, Goa

Subject : Techno-Commercial Offer for Automatic Retractable Roof

Dear Sir ,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	NIHVA Introduction	1
B.	Commercial Offer	1
C.	Technical Specification	1
D.	General Conditions	2
E.	Terms & Condtions	2



A) Why to Choose NIHVA?

1 Prominent Brand for Automation products
2 Pioneers in offering Intelligent, Innovative and Economical Solutions.
3 Specilized in Integrated solutions of Automations.
4 Continuous Improvement in - Change, Communication, Gratitude, Performance & Leadership
5 Integrity, Quality & Commitment
6 Innovation & Novelty in Design
7 Experinced & Skilled Manpower
8 Customer Centric Organization to deliver Best Quality Products & On Time Services.

B) Commercial Offer

Sr No	Description	Size (mm)	Qty	Supply & Installation Charges in INR	
			(Nos)	Unit Price	Total Amount
1	**Automatic Retractable Roof**	• 6000 X 6000 X 800 X 3 panel • One side opening • Installation Inclusive	1	14,20,000	14,20,000
		Total without Tax			**14,20,000**
2		GST Extra @ 18%	18%		**Extra At Actual**
3		P&F Charges @ 3%	3%		**Extra At Actual**
4		Transportation Charges			**In client Scope**
5		Lifting Equipment required @ desired floor			**In client Scope**
6		Support Structure if required @ site			**In client Scope**
7		Unloading Charges @ Site			**In client Scope**

C) Technical Specification

Detailed Technical-NIHVA Make Automatic Retractable Roof

NIHVA Make Automatic sliding Retractable roof with European make electric drive inbuilt control, safety sensor, temperature sensor, electromagnetic limit switch. The power supply 450W 230V & 50/60hz. The minimum speed of operation should be 0.28m/s with a driving force of 900N. The minimum working temp should be- 20 degree and maximum working temperature should be 50 degrees. The dimension of motor should be approximately 330x210x303 mm with an utmost weight of 13kg. The control unit should be pull out unit protected by casing and buffer batteries. The synchronisation should be Master/slave system with control system with pendant and remote controlled. The minimum programming level can be 8. There should be option of home automation connectivity. It should come with optional and mandatory feature like receiver, transmitter, photocell and flashing light. The glazing tensile stress and strength should be more than 60 MPa with maximum 6% elongation. The glazing dielectric strength should be 35 kV/mm as per IEC 60243-1. The Vicat softening temperature should be 148-degree Celsius as per ISO 306. The heat deflection temperature under load of 1.80 MPa is 127-degree Celsius with minimum impact strength of 11 kJ/mm. The structural material Grade of AL should be AL 6060-T4, AL 6060- T6. The Aluminium profile should be Specially extruded Non corrosive AL hollow profile with material composition of AL (%) > 98% Si (%) = 0.30 (min) – 0.70 (max). The dimensional tolerance should not be more than ± 20mm and the angularity tolerance should not be more than ± 1%.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Short Technical-NIHVA Make Automatic Retractable Roof
1. Polycarbonate Compact Clear/Embossed 3.0 mm Thick
2. Profile : Powder Coated AL Frame UV protected both side
3. Guide : AL Guide
4. Interlocking
5. Motors Mechanism a) 2 Remote Controlled b) Single Phase Bi-directional Motor c) Speed- 09-12m/min d) Power- As per Roof Dimension e) Mechanical Limit Switch f) Rack and Pinion Arrangement g) Italian/German Make
6. EPDM Gaskets and sealants
7. SS Fastners

D) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

E) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.

Payment : 70% Advance along with Confirmed Purchase Order.
25% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning.

Validity : Validity of offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

Design Clause : NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.

Compensation Clause : Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd