NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

L&T Hydrocarbon Engineering Ltd
West Block, Ground Floor,
L&T Knowledge City, N.H. No. 8,
Vadodara, Gujarat, India.

Date : 24.12.2020
Quote NO : SQT20-21.0021R6
Kind Attn : Mr. Vaidik Miyani
Email Id : VAIDIK.MIYANI@larsentoubro.com
Contact No: **8347789960**

Subject : Quotation for Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Dock Leveller 6 Ton including Power Pack/Motor Suitatble for Hazardous area as specified by LTHE	1820	5000	2	1,048,000	2,096,000	In LTHE Scope	
2	Mandatory Spares as per attached list				295,000	295,000		
3	**Extended Warranty charges as specified by LTHE**							
	For the year 2020 - 2021				Inclusive in Supply			
	For the year 2021 - 2022			1	45,000	45,000		
	For the year 2022 - 2023			1	65,000	65,000		
	For the year 2023 - 2024			1	85,000	85,000		
				Total		**2,586,000**		**-**
	P&F Charges					**20,000**		
	Total Without Taxes					**2,606,000**		**-**
	GST Extra @ 18%			18%		469,080		-
	Total With Taxes					**3,075,080**		**-**
	Total Supply + Installation With Taxes							**3,075,080**
4	Transportation Charges					**Extra at Actual**		
5	Unloading Charges @ Site					**In Client Scope**		
	Note : A) Third Party Inspection charges will be in Client Scope							
	B) Extended warranty and AMC will be applicable after purchase of recommonded spares by Client only.							
	C) If any additional Certificate required extra charges will be applicable							

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel - Standpost Mounted
5	Loading platform height from road	900 mm - Ideally it should be 1200 mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	1820 mm x 5000 mm
8	Lip size (W x L)	1820 x 250 mm
9	Shut Height	600 mm
10	Overall length	1820 mm x 5000 mm + Lip Length (250mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 1870mm x (L)5000 mm x (D)600 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Pair of Dock Bumper	Included

Optional Charges - Extra

We are proposing hereby complete AMC as per below charges applicable.
This is optional for LTHE

AMC charges for the year 2021-22	202,500.00
AMC charges for the year 2022-23	270,000.00
AMC charges for the year 2023-24	405,000.00

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1	Installation will be in LTHE Scope : We don't require any C Channel beside shown in the drawing for preparation of Dock Leveller+ Pit. Rest NIHVA will supply the necessary Anchor Bolts, Welding Rods etc.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	
2	Our motor is Single Phase only, we will require Single phase Plug in point with earthing near the Dock Leveller control panel,nothing else is require. The Conduit will be in LTHE scope form Pit to Control panel.	
3	Push Buttons, Anchor bolts for necessary to install the dock leveller will be supplied by NIHVA.	
4	Conduit form Dock Leveller Pit to Control unit location shall be in LTHE Scope.	

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 10 to 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: A) Advance 50% of the basic value of Purchase Order (excluding GST) on fulfilment of below conditions: • Receipt of an unconditional Purchase Order acceptance copy • Receipt of Advance Bank Guarantee (ABG) @no cost to LTHE, as per LTHE format; valid till 3 months after Purchase Order delivery date goods. **Note : Manufacturing will start only after receipt of Advance payment and Drawing Approval.** B) Remaining 50% of the basic order value, plus 100% taxes shall be released after dispatch Note
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply + Extended warranty for 3 years with charges applicable as specified in above offer. AMC will be optional if agreed by LTHE

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd