WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
M/S QUALITY INFRASTRUCTURE PVT LTD	
Address:	
1, RAJHANS COMPLEX, 1ST FLOOR, G.I.D.C., CHAR RASTA, VAPI-396195 STATE:-GUJARAT [24]	

PO Number:	261/QIPL/GUJ/21-22- REVISION-1	W. O. No-	SO/21-22/0126
PO Dated :	05-02-2022	W. O. Date	07-02-2022
PO Received Date:	07-02-2022	Sales Co ordinator	Pradeep S
Ref. Quotation:	SQT.21.22.0242 R3 DATED-04/02/2022	Front Sales Person	Shrikant Mirkute

Dispatch Address:

M/S QUALITY INFRASTRUCTURE PVT LTD
C/O DHANUKA AGRTECH LTD PLOT NO-D-3/1/A, DAHEJ-III INDUSTRIAL ESTATE, TA-VAGARA, DAHEJ-392110, DIST-BHARUCH STATE-GUJARAT [24]

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Single Skin Rolling Shutter - Gear Operated Size : W 2500 mm X H 3500 mm	**Description:** Gear Operated Rolling Shutter with GI Slats with thickness of 1.2 mm. **Mounting Location area :** Inside area / Outside area **Mounting Surface:** Side Brackets: Optional = On Concrete /Steel & Side **Curtain Panel:** The panel made of 1.2 mm thick GI **Curtain panel size:** 75mm wide **Curtain Profile:** Curved / Flat - Confirm with client at time of drawing approval . **Bottom Profile:** M. S. Plate 100 mm x 2.5 mm thick with angle stiffener **Side Guide Profile:** M.S." U" Shaped profile **Roller Shaft:** M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h **Side Brackets:** MS Plate 3 mm to 10 mm thick, as per the opening dimension. **Hood Cover:** Made of GI Sheet Thickness 0.6 mm. **Surface finish:** Powder Coated **Drive Unit & Mounting Type: Electric Motor** -Gear Aseembly	Nos	5		Included	-	Pending
2	Single Skin Rolling Shutter - Gear Operated Size : W 3000 mm X H 3500 mm	Same as above	Nos	7		Included	-	Pending
3	Single Skin Rolling Shutter - Gear Operated Size : W 2000 mm X H 3500 mm	Same as above	Nos	1		Included	-	Pending
4	Single Skin Rolling Shutter - Gear Operated Size : W 2000 mm X H 3000 mm	Same as above	Nos	1		Included	-	Pending
						Total	-	

Non standard items/extra requirement, if any:	

B Commerical Terms:

1	Payment Terms:	30% Advance along with PO, 50% before dispatch against P.I and balance 20% will be releaed after 15 days from the satisfactory work completion and measurement certified		
2A	Delivery Date as per PO:	Within 4-5 weeks from after drawing approval	2B. Required Delivery Date:	
3A	Transportation Scope:	NIHVA (Included)	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	NIHVA	5B. Loading Charges:	
6A	Unloading Scope:	CLIENT	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	CLIENT	7B. Available Lifting Equipments:	
8	Warranty:	12 months from the date of supply.		
9A	Height arrangement Scope:	CLIENT	9B. Available Equipments for working at Site:	
10	Electricity Supply:	CLIENT		
11	GST:	As Applicable		
12A	Installation Scope:	NIHVA	12B. Installation required date:	
13	Mode of import:	NA		
14	HSS:	No		
15	Documentation Required:	Standard Handover Documents		
16A	Total site visits required:		16B. Site visit charges:	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	S.M.	G.P.	07-02-2022